

**GENERAL NOTES**

1. BEFORE STARTING ANY EXCAVATIONS, THE CONTRACTOR SHALL CALL "J.U.L.I.E" AT (800)892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED).
  2. CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE VILLAGE OF HILLSIDE.
  3. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
  4. THE CONTRACTOR SHALL NOTIFY MR. JOSEPH PISANO (708) 202-3434 AT THE VILLAGE OF HILLSIDE A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.
  5. EXACT LOCATIONS AND LIMITS OF REMOVALS SHALL BE DETERMINED IN THE FIELD BY THE FIELD ENGINEER AT THE TIME OF CONSTRUCTION.
  6. CENTERLINES ARE APPROXIMATE AND SHALL BE USED FOR LOCAL REFERENCE ONLY.
  7. NO STOCKPILING OF MATERIAL ON THE JOB SITE IS PERMITTED.
  8. DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.
  9. THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THE PROJECT.
  9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING ALL WORK OPERATIONS AND EQUIPMENT ARE LOCATED AND PERFORMED OUTSIDE OF THE PAVEMENT AREAS. ONLY SHORT-TERM OR TEMPORARY LANE CLOSURES WILL BE PERMITTED FOR DELIVERY OF MATERIALS. NO OVERNIGHT LANE CLOSURES ARE PERMITTED DURING CONSTRUCTION.
  10. ALL SOILS AND MATERIALS EXCAVATED SHALL BE RE-USED OR SPREAD ON SITE AS DIRECTED BY THE ENGINEER AT THE TIME OF CONSTRUCTION.
11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY REPAIRS OR RESTORATION TO ITEMS DAMAGED BY CONSTRUCTION OR CONSTRUCTION EQUIPMENT AT NO ADDITIONAL COST TO THE CONTRACT. THE DAMAGED AREAS SHALL BE RESTORED TO THE SATISFACTION OF THE VILLAGE OF HILLSIDE AND THE FIELD ENGINEER. ALL RESTORATION WORK SHALL BE INCLUDED IN THE COST OF THE CONTRACT.
12. ALL WORK PERFORMED RELATIVE TO THIS IMPROVEMENT SHALL COMPLY WITH ALL APPLICABLE RULES AND REGULATIONS OF O.S.H.A.
13. THE CONTRACTOR SHALL REMOVE ALL CONSTRUCTION DEBRIS AND LOOSE MATERIALS FROM THE ROADWAY AND ADJACENT AREAS AT THE CLOSE OF EACH WORKING DAY TO SATISFACTION OF THE FIELD ENGINEER. THIS WORK SHALL BE INCLUDED IN THE COST OF THE CONTRACT AND NO ADDITIONAL PAYMENT SHALL BE MADE.
14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DAMAGE TO ANY UTILITY CAUSED BY CONSTRUCTION ACTIVITIES. SHOULD ANY DAMAGES OCCUR, THE CONTRACTOR SHALL NOTIFY THE FIELD ENGINEER, THE VILLAGE OF HILLSIDE, AND THE UTILITY OWNER IMMEDIATELY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DELAYS, REPAIR COSTS, AND ANY OTHER FEES ASSOCIATED WITH THE REPAIR OF THE UTILITY. THIS WORK IS NOT INCLUDED IN THIS CONTRACT AND NO PAYMENT SHALL BE MADE.
15. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL RESTORATION OF AREAS DAMAGED BY EQUIPMENT ACCESSING THE SITE OR THE PLACEMENT OF ITEMS ON SITE. THE AREAS SHALL BE RESTORED WITH 4" OF TOPSOIL AND CLASS 4A PROFILE NATIVE GRASS PLANTINGS. THIS WORK SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCLUDED IN THE COST OF PAY ITEM 50200100 STRUCTURAL EXCAVATION.

**INDEX OF SHEETS**

- 1 TITLE SHEET
- 2 GENERAL NOTES, INDEX, STANDARDS LIST
- 3 SUMMARY OF QUANTITIES
- 4 SITE PLAN
- 5 PROPOSED MONUMENT PLAN
- 6 MONUMENT, TYPE A ELEVATION PLAN
- 7 MONUMENT, TYPE B ELEVATION PLAN
- 8 PILE DETAILS
- 9 MONUMENT DETAILS
- 10 LANDSCAPING PLAN
- 11 LANDSCAPING DETAILS
- 12 SOIL BORING LOGS

**IDOT STANDARDS**

- 701101-03: OFF-RD OPERATIONS, MULTILANE, 15' TO 24' FROM PAVEMENT EDGE
- 701106-02: OFF-RD OPERATIONS, MULTILANE, MORE THAN 15' AWAY
- 701427-01: LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATION
- 701901-02: TRAFFIC CONTROL DEVICES

**GENERAL SPECIFICATIONS**









THE WORK SHALL BE COMPLETED IN ACCORDANCE WITH THE APPLICABLE PORTIONS OF THE FOLLOWING:

"STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", ADOPTED JANUARY 1, 2012, "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS", ADOPTED JANUARY 1, 2013.

"HIGHWAY STANDARDS" ILLINOIS DEPARTMENT OF TRANSPORTATION.

"MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES", 2009 EDITION

**LEGEND**

-  EXISTING TREE
-  EXISTING UTILITY STRUCTURE
-  EXISTING GUARDRAIL
-  EXISTING LIGHT POLE
-  EXISTING SIGN
-  EXISTING CONTROLLER
-  EXISTING TRAFFIC POLE
-  PROPOSED MONUMENT

P.L. NAME: [unclear] DATE: [unclear] TIME: [unclear]

DESIGNED - DWP  
DRAWN - DWP  
CHECKED - AHN  
DATE - 12/17/2012

SHEET NAME: [unclear] PLOT SCALE: 1/8" = 1'-0" PLOT DATE: [unclear]	DESIGNED - DWP DRAWN - DWP CHECKED - AHN DATE - 12/17/2012	REVISED - REVISED - REVISED - REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>VILLAGE OF HILLSIDE</b> <b>MANNHEIM ROAD STREETSCAPE &amp; I-290 BRIDGE IMPROVEMENTS</b> <b>GENERAL NOTES</b>	F.A.P. RTE. 330	SECTION 06-00045-00-LS	COUNTY COOK	TOTAL SHEETS 12	SHEET NO. 02	CONTRACT NO. 63783
				SCALE: AS SHOWN    SHEET NO. 02 OF 12 SHEETS    STA.    TO STA.	[ILLINOIS]					