SUMMARY OF QUANITITIES

	SPECIAL PROVISION	PAY ITEM	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
						0031	0040	0042
*		21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	106	106		
		50200100	STRUCTURE EXCAVATION	CU YD	55.0		55.0	
		50300225	CONCRETE STRUCTURES	CU YD	37.0		37.0	
		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3260.0		3260.0	
		51201400	FURNISHING STEEL PILES, HP 10X42	FOOT	81.0		81.0	
		51202305	DRIVING PILES	FOOT	81.0		81.0	
		51203400	TEST PILE, HP 10X42	EACH	1.00		1.00	
		51204650	PILE SHOES	EACH	4.0		4.0	
		67100100	MOBILIZATION	L SUM	1.0		1.0	
*		K0012993	PERENNIAL PLANTS, ORNAMENTAL TYPE, 3-GALLON POT	UNIT	4.66	4.66		
*	x	K0026850	PERRENIAL PLANT CARE	SQ YD	700.00	700.00		
*	x	K0029634	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	5.00	5.00		
*	x	K1005481	SHREDDED BARK MULCH 3"	SQ YD	135	135		
*	x	XX007415	MONUMENT, TYPE A	EACH	1.0		1.0	
*	x	XX007416	MONUMENT, TYPE B	EACH	1.0		1.0	
	x	Z0013798	CONSTRUCTION LAYOUT	L SUM	1.0		1.0	

* SPECIALTY ITEMS

FILE NAME = c:\pwidot\work\d0_rst_dwlr\dwg\751101_ill_2061-rt-290_01.dgn

USER NAME = Peter01040	DESIGNED - DWP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
	DRAWN - DWP	REVISED -	
PLOT SCALE = 40.0000 ' / in.	CHECKED - AHN	REVISED -	
PLOT DATE = 01\03\2013	DATE - 12/17/2012	REVISED -	

VILLAGE OF HILLSIDE
MANNHEIM ROAD STREETSCAPE & I-290 BRIDGE IMPROVEMENTS
SUMMARY OF QUANTITIES

SCALE: AS SHOWN | SHEET NO. 03 OF 12 SHEETS | STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	06-00045-00-LS	COOK	12	03
		CONTRACT NO. 63783		
		ILLINOIS		

LAYOUT / DRAWN / REVIEWED