



FULLERTON AVENUE ALIGNMENT DATA

DESCRIPTION	STATION	NORTHING	EASTING
BEGINNING OF ALIGNMENT	14+28.96	1913707.91	1081895.70
POINT OF TANGENT	17+16.56	1913715.87	1082183.18
POINT OF TANGENT	20+22.87	1913723.80	1082489.39
END OF ALIGNMENT	21+41.97	1913726.47	1082608.45

SITE BENCHMARKS

NUMBER	DESCRIPTION	ELEVATION
1	CROSS CUT IN SIDEWALK NEAR NORTHWEST CORNER OF VILLA AVENUE AND FULLERTON AVENUE.	674.57
2	CROSS CUT IN LIGHT POLE BASE	671.25
3	CHISELED "X" ON EXISTING WINGWALL	678.81

SOURCE BENCHMARK

DuPAGE COUNTY BENCHMARK: YK03001
 TOWNSHIP: YORK
 DESCRIPTION: THE STATION IS AT THE SOUTHWEST CORNER OF THE INTERSECTION OF NORTH AVENUE AND VILLA AVENUE, 58.0 FT. SOUTH OF THE CENTERLINE OF NORTH AVENUE AND 59.80 FT. WEST OF THE CENTERLINE OF VILLA AVENUE. A BRONZE DISK MONUMENT ESTABLISHED IN CONCRETE BASE OF TRAFFIC CONTROL LIGHT STAMPED "DuPAGE COUNTY MAPS AND PLATS".
 STATION ELEVATION: 679.8569 FT.
 VERTICAL DATUM: NGVD 29

PLOT DATE: Jan 03, 2013
 FILENAME: H:\11-TP\3067-Fullerton Bridge\PLAN-ENG\RF-V-1311-TP-3067_Site_2013-01-03.dwg



USER NAME *	DESIGNED - JV/AS	REVISED -
PLOT SCALE *	DRAWN - CS/DB	REVISED -
PLOT DATE * Jan 03, 2013	CHECKED - SV	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

FULLERTON AVENUE BRIDGE OVER SALT CREEK
 ALIGNMENT, TIES AND BENCHMARKS

SCALE: 1"=50' SHEET NO. 1 OF 1 SHEETS STA. 14+28.96 TO STA. 21+41.97

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-01*20-00-BR	DuPAGE	38	6
CONTRACT NO. 63785			ILLINOIS FED. AID PROJECT	