

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	HPP	NHS	HPP		HPP					
				FED 80% STATE 20%	FED 80% STATE 20%	FED 80% STATE 10%/CITY 10%	FED 80% STATE 10%/CITY 10%	FED 80% STATE 10%/CITY 10%	FED 80% STATE 10%/CITY 10%	FED 80% STATE 10%/CITY 10%	FED 80% STATE 10%/CITY 10%	FED 80% STATE 10%/CITY 10%	FED 80% STATE 10%/CITY 10%
				ROADWAY	ROADWAY	TRAFFIC SIGNALS	EARTH EXCAVATION	EVSCS	LIGHTING ORN HWY MU PATH	MULTI-USE PATH	LANDSCAPE	SIDEWALK	FLASHING BEACON
				0003	0003	0021	0003	0021	0021	0028	0031	0021	0021
60107600	PIPE UNDERDRAINS 4"	FOOT	4,092		1,717						2,375		
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4		4								
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	7		7								
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5		5								
60224459	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2		2								
60236200	INLETS, TYPE A, TYPE B GRATE	EACH	8								8		
60240301	INLETS, TYPE B, TYPE B GRATE	EACH	22		13						9		
60255500	MANHOLES TO BE ADJUSTED	EACH	8		8								
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2		2								
60260100	INLETS TO BE ADJUSTED	EACH	2		2								
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	6		6								
60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3		3								
60262900	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1		1								
60500040	REMOVING MANHOLES	EACH	38		38								
60500060	REMOVING INLETS	EACH	51		51								
60600605	CONCRETE CURB, TYPE B	FOOT	222.0		222.0								
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	317.0		317.0								
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	6,349.0		6,349.0								
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	15,558		15,558								
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SO FT	6,529		6,529								
60624600	CORRUGATED MEDIAN	SO FT	1,028		1,028								
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	4		4								
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18		18								
67100100	MOBILIZATION	L SUM	1		1								
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1								
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1		1								
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		1								
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1								
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		1								
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	90		90								
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	36		36								
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	78		78								
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	17,366		17,366								
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	300		300								
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	181		181								
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2,213		2,213								

Δ SPECIALITY ITEM ** 100% STATE

FILE NAME =	USER NAME = dssadd	DESIGNED - JWM	REVISED -
c:\p\work\p\p\p\p\dssadd\dms7949\0264750-plt-800-tpgs5-111.dgn		DRAWN - JWM	REVISED -
		CHECKED - RCH	REVISED -
		DATE - *SUBDATE*	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 3 OF 6 SHEETS STA. TO STA.

F.A.P. RTE. 303	SECTION 41R	COUNTY WINNEBAGO	TOTAL SHEETS 327	SHEET NO. 7
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT			CONTRACT NO. 64750	