

EARTHWORK SCHEDULE US BUS 20 (CONTINUED)

BEGIN STATION	END STATION	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
277+50.00	278+00.00	37	21	28	211	-183
278+00.00	278+50.00	67	14	50	148	-98
278+50.00	279+00.00	61	9	46	83	-37
279+00.00	279+51.14	46	3	35	35	0
279+51.14	280+00.00	88	7	66	8	58
280+00.00	280+50.00	111	11	83	1	82
280+50.00	281+00.00	90	9	68	5	63
281+00.00	281+50.00	94	9	71	5	66
281+50.00	282+00.00	100	8	75	10	65
SUB TOTAL		26,140	5,057	19,612	8,001	11,611

EARTHWORK SCHEDULE WEST SUNSET AVENUE

BEGIN STATION	END STATION	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
13400+50.00	13400+74.81	66	10	50	0	50
SUB TOTAL		66	10	50	0	50

EARTHWORK SCHEDULE INDEPENDENCE AVENUE (SOUTH)

BEGIN STATION	END STATION	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
13600+50.00	13601+00.00	52	9	39	7	32
13601+00.00	13601+48.33	96	11	72	4	68
13601+48.33	13602+00.00	180	16	135	0	135
13602+00.00	13602+48.32	266	18	200	0	200
13602+48.32	13603+00.00	312	19	234	0	234
SUB TOTAL		906	73	680	11	669

EARTHWORK SCHEDULE INDEPENDENCE AVENUE (NORTH)

BEGIN STATION	END STATION	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
13500+50.00	13501+00.00	166	10	125	2	123
13501+00.00	13501+50.00	95	17	71	6	65
SUB TOTAL		261	27	196	8	188

* ASSUME 25% FOR SHRINKAGE

FILE NAME =	USER NAME = dossdd	DESIGNED - JWM	REVISED -
et:\pwork\pwork\dot\dossdd\dms67949\0264750-sh-t-schedule-(pgs22-36).dgn		DRAWN - JWM	REVISED -
		CHECKED - RCH	REVISED -
		DATE - \$SUBDATE\$	REVISED -

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	41R	WINNEBAGO	327	31
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT			CONTRACT NO. 64750	