

EARTHWORK SCHEDULE CENTRAL AVENUE - TEMPORARY PAVEMENT

BEGIN STATION	END STATION	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
11998+93.00	12000+00.00	53	8	40	2	38
12000+00.00	12000+50.00	15	2	11	1	10
12000+50.00	12001+00.00	18	3	14	1	13
12001+00.00	12001+50.00	37	5	28	1	27
12001+50.00	12002+00.00	39	5	29	1	28
12002+00.00	12002+50.00	40	5	30	1	29
12002+50.00	12003+00.00	37	5	28	1	27
12003+00.00	12003+50.00	18	3	14	1	13
12003+50.00	12004+00.00	0	0	0	0	0
12004+00.00	12004+50.00	21	3	16	1	15
12004+50.00	12005+00.00	40	5	30	1	29
12005+00.00	12005+50.00	37	5	28	1	27
12005+50.00	12006+00.00	38	5	29	1	28
12006+00.00	12006+50.00	46	5	35	1	34
12006+50.00	12007+00.00	49	6	37	1	36
12007+00.00	12007+50.00	30	3	23	1	22
12007+50.00	12008+00.00	27	1	20	1	19
SUB TOTAL		545	69	412	17	395

EARTHWORK SCHEDULE CENTRAL AVENUE - STAGE 1

BEGIN STATION	END STATION	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
12000+00.00	12000+50.00	0	0	0	0	0
12000+50.00	12001+00.00	11	5	8	13	-5
12001+00.00	12001+50.00	95	11	71	13	58
12001+50.00	12002+00.00	157	12	118	0	118
12002+00.00	12002+50.00	144	9	108	1	107
12002+50.00	12003+00.00	170	7	128	4	124
12003+00.00	12003+50.00	99	4	74	3	71
12003+50.00	12004+00.00	0	0	0	0	0
12004+00.00	12004+50.00	186	14	140	0	140
12004+50.00	12005+00.00	268	19	201	0	201
12005+00.00	12005+50.00	173	16	130	0	130
12005+50.00	12006+00.00	211	20	158	0	158
12006+00.00	12006+50.00	195	17	146	0	146
12006+50.00	12007+00.00	132	14	99	0	99
12007+00.00	12007+50.00	133	21	100	0	100
SUB TOTAL		1,974	169	1,481	34	1,447

* ASSUME 25% FOR SHRINKAGE

FILE NAME =	USER NAME = dossed	DESIGNED - JWM	REVISED -
ct:\pwork\pwork\dot\dossed\dms67949\0264750-sh-t-schedule-(pgs22-36).dgn		DRAWN - JWM	REVISED -
		CHECKED - RCH	REVISED -
		DATE - \$SUBDATE\$	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. 11 OF 15 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	41R	WINNEBAGO	327	32
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT			CONTRACT NO. 64750	