

EARTHWORK SCHEDULE TAY STREET

BEGIN STATION	END STATION	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
14101+50.00	14102+00.00	35	15	26	7	19
14102+00.00	14102+50.00	14	14	11	22	-11
14102+50.00	14103+00.00	9	20	7	50	-43
SUB TOTAL		58	49	44	79	-35

EARTHWORK SCHEDULE OAKWOOD AVENUE

BEGIN STATION	END STATION	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
14200+50.00	14201+00.00	306	15	230	0	230
14201+00.00	14201+50.00	154	14	116	0	116
14201+50.00	14202+00.95	75	23	56	6	50
14202+00.95	14202+50.00	17	17	13	15	-2
14202+50.00	14203+00.00	35	13	26	10	16
SUB TOTAL		587	82	441	31	410

EARTHWORK SCHEDULE LAKIN TERRACE

BEGIN STATION	END STATION	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
14300+50.00	14301+00.00	228	19	171	0	171
14301+00.00	14301+50.00	158	16	119	0	119
14301+50.00	14302+00.00	105	13	79	0	79
14302+00.00	14302+50.00	43	8	32	2	30
SUB TOTAL		534	56	401	2	399

EARTHWORK SCHEDULE AVON STREET - TEMPORARY PAVEMENT

BEGIN STATION	END STATION	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
12100+00.00	12100+50.00	22	4	17	1	16
12100+50.00	12101+00.00	35	1	26	1	25
12101+00.00	12101+50.00	61	5	46	1	45
12101+50.00	12102+00.00	66	9	50	1	49
12102+00.00	12102+49.58	54	8	41	1	40
12102+49.58	12103+00.00	55	8	41	1	40
12103+00.00	12103+50.00	63	8	47	1	46
12103+50.00	12104+00.00	32	4	24	1	23
12104+00.00	12104+50.00	0	0	0	0	0
12104+50.00	12105+00.00	12	2	9	0	9
12105+00.00	12105+50.00	25	2	19	1	18
12105+50.00	12106+00.00	27	0	20	1	19
12106+00.00	12106+50.00	33	2	25	1	24
12106+50.00	12107+00.00	41	4	31	1	30
12107+00.00	12107+50.00	42	5	32	1	31
12107+50.00	12108+00.00	21	3	16	1	15
SUB TOTAL		589	65	444	14	430

* ASSUME 25% FOR SHRINKAGE

McDonough Associates Inc.
Engineers / Architects
130 East Randolph Street, Chicago, Illinois 60601

FILE NAME =	USER NAME = dossed	DESIGNED - JWM	REVISED -
ci:\pw\work\p\dot\dossed\dms67949\0264750-sh-t-schedule-(pgs22-36).dgn		DRAWN - JWM	REVISED -
		CHECKED - RCH	REVISED -
		DATE - \$SUBDATE\$	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 13 OF 15 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	41R	WINNEBAGO	327	34
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT			CONTRACT NO. 64750	