

EARTHWORK SCHEDULE AVON STREET - STAGE 1

BEGIN STATION	END STATION	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
12101+00.00	12101+50.00	44	10	33	2	31
12101+50.00	12102+00.00	89	11	67	2	65
12102+00.00	12102+49.58	143	6	107	0	107
12102+49.58	12103+00.00	150	10	113	1	112
12103+00.00	12103+50.00	168	26	126	8	118
12103+50.00	12104+00.00	97	16	73	8	65
12104+00.00	12104+50.00	0	0	0	0	0
12104+50.00	12105+00.00	109	9	82	0	82
12105+00.00	12105+50.00	198	17	149	0	149
12105+50.00	12106+00.00	163	9	122	0	122
12106+00.00	12106+50.00	137	4	103	1	102
12106+50.00	12107+00.00	114	7	86	4	82
12107+00.00	12107+50.00	66	9	50	9	41
12107+50.00	12108+00.00	15	5	11	24	-13
SUB TOTAL		1,493	139	1,122	59	1,063

EARTHWORK SCHEDULE AVON STREET - STAGE 2

BEGIN STATION	END STATION	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
12100+50.00	12101+00.00	18	0	14	4	10
12101+00.00	12101+50.00	25	0	19	16	3
12101+50.00	12102+00.00	36	1	27	22	5
12102+00.00	12102+49.58	55	1	41	9	32
12102+49.58	12103+00.00	59	5	44	6	38
12103+00.00	12103+50.00	87	12	65	5	60
12103+50.00	12104+00.00	57	8	43	1	42
12104+00.00	12104+50.00	0	0	0	0	0
12104+50.00	12105+00.00	76	5	57	0	57
12105+00.00	12105+50.00	116	6	87	2	85
12105+50.00	12106+00.00	88	3	66	2	64
12106+00.00	12106+50.00	84	3	63	8	55
12106+50.00	12107+00.00	68	1	51	15	36
12107+00.00	12107+50.00	44	1	33	16	17
SUB TOTAL		813	46	610	106	504

EARTHWORK SCHEDULE WB CROSS OVER

BEGIN STATION	END STATION	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
3000+50.00	3001+00.00	696	114	522	49	473
3001+00.00	3001+50.00	722	154	542	164	378
3001+50.00	3002+00.00	517	207	388	216	172
3002+00.00	3002+50.00	351	202	263	117	146
3002+50.00	3003+00.00	281	169	211	77	134
3003+00.00	3003+50.00	330	130	248	20	228
SUB TOTAL		2,897	976	2,174	643	1,531

EARTHWORK SCHEDULE OAKLEY/IRVING ALLEY

BEGIN STATION	END STATION	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
13+75.00	15+00.00	59	6	44	0	44
15+00.00	16+25.00	62	9	47	0	47
SUB TOTAL		121	15	91	0	91

EARTHWORK SCHEDULE CRUSADER CLINIC ALLEY

BEGIN STATION	END STATION	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
23+84.00	25+00.00	119	34	89	2	87
25+00.00	26+12.00	136	33	102	1	101
SUB TOTAL		255	67	191	3	188

\* ASSUME 25% FOR SHRINKAGE

FILE NAME =	USER NAME = dosddd	DESIGNED - JWM	REVISED -
ct:\pw\work\p\dot\dosddd\dms67949\0264750-sh-t-schedule-(pgs22-36).dgn		DRAWN - JWM	REVISED -
		CHECKED - RCH	REVISED -
		DATE - \$SUBDATE\$	REVISED -

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	41R	WINNEBAGO	327	35
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT			CONTRACT NO. 64750	