



••SEE NOTE 2

REMOVAL LIMITS
STATION 12100+84.05

MATCH LINE
(SEE SHEET EX-6)

MATCH LINE (SEE SHEET EX-6)

MATCH LINE (SEE SHEET EX-6)

MATCH LINE (SEE SHEET EX-6)

44000600 SIDEWALK REMOVAL
 STA. 12099+91.84 TO 12100+52.33, LT - 313.9
 STA. 12100+89.40 TO 12102+27.04, LT - 563.4
 STA. 12102+45.85 TO 12103+00.24, LT - 240.7
 STA. 12100+85.61 TO 12102+40.43, RT - 688.5
 STA. 12102+71.71 TO 12103+00.12, RT - 122.9
 TOTAL - 1929.9 SQ FT

44000100 PAVEMENT REMOVAL
 STA. 12100+84 TO 12103+00 - 742.2
 TOTAL - 742.2 SQ YD

44000500 COMBINATION CURB AND GUTTER REMOVAL
 STA. 12098+86.21 TO 12099+53.62, LT - 67.4'
 STA. 12100+17.40 TO 12100+53.79, LT - 47.0'
 STA. 12100+88.23 TO 12102+27.19, LT - 174.7'
 STA. 12102+46.41 TO 12103+00.22, LT - 61.9'
 STA. 12100+83.38 TO 12102+34.92, RT - 175.2'
 STA. 12102+63.91 TO 12103+00.22, RT - 36.9'
 TOTAL - 563.1'

NOTE:
 1. SEE SHEET EX-1 FOR REMOVAL LEGEND
 2. ALL ITEMS BEYOND THE IMPROVEMENT LIMITS REMOVED FOR TEMPORARY PAVEMENT INSTALLATION INCLUDING BUT NOT LIMITED TO: SIDEWALK, DRIVEWAYS, AND CURB & GUTTER, SHALL BE REPLACED IN KIND UPON TEMPORARY PAVEMENT REMOVAL. THE COST SHALL BE INCLUDED IN THE TEMPORARY PAVEMENT REMOVAL. SEE MOT PRE-STAGE SHEETS FOR ADDITIONAL REMOVAL ITEMS.

LEGEND	
/// /// ///	TEMPORARY CONSTRUCTION EASEMENT
— — — — —	EXISTING R.O.W.
- - - - -	PROPOSED R.O.W.
- xxx - xxx -	STORM SEWER REMOVAL
[A]	STRUCTURE TO BE ADJUSTED
[R]	STRUCTURE TO BE REMOVED
[REC]	STRUCTURE TO BE RECONSTRUCTED
[X]	PAVEMENT REMOVAL
[]	DRIVEWAY PAVEMENT REMOVAL
[]	COMBINATION CONCRETE CURB AND GUTTER REMOVAL
[]	SIDEWALK REMOVAL
[]	CONCRETE REMOVAL
[]	BITUMINOUS REMOVAL
[]	BARRIER CURB REMOVAL
[]	BUILDING TO BE REMOVED (BY OTHERS)

FILE NAME =	USER NAME = dosddd	DESIGNED - JWM	REVISED -
et:\pw\work\p\dot\dosddd\0317613\0264750-sht-rem062.dgn		DRAWN - JPF	REVISED -
	PLOT SCALE = 40.0000' / in.	CHECKED - RCH	REVISED -
	PLOT DATE = Mon Dec 17 13:35:06 2012	DATE - \$SUBDATE\$	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

EXISTING REMOVAL PLAN
AVON STREET
SCALE: SHEET NO. 15 OF 18 SHEETS STA.12100+84.05 TO STA. 12103+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	41R	WINNEBAGO	327	62
CONTRACT NO. 64750			FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT	

McDonough Associates Inc.
Engineers / Architects
130 East Randolph Street, Chicago, Illinois 60601