

101

M140 M240 M240 07A0 M240 M240 67P0 07A0 07A0 07A0 M240 M240
 01 01 01 01 01 01 01 01 01 01 01 01

| PAY ITEM NUMBER | DESCRIPTION | UNIT | TOTAL QUANTITY | 80% FED 20% STATE ROADWAY 0004 URBAN | 80% FED 20% CITY BIKEPATH 0028 URBAN | 80% FED 20% STATE BRIDGE 0014 URBAN | 100% STATE HIGHWAY LIGHTING 0021 URBAN | 80% FED 20% STATE SPECIAL BRIDGE 0040 URBAN | 80% FED 10% STATE 10% CITY TRAFFIC SIGNALS 0021 URBAN | 100% CITY TRAFFIC SIGNALS 0021 URBAN | WATER MAIN 100% STATE UTILITY 0043 URBAN | SAN SEWER 100% STATE UTILITY 0043 URBAN | LANDSCAPE 100% STATE ROADWAY 0031 URBAN | LANDSCAPE 80% FED 20% STATE ROADWAY 0031 URBAN | 80% FED 20% STATE DEMOLITION 0044 URBAN |
|-----------------|---------------------------------------|-------|----------------|--------------------------------------|--------------------------------------|-------------------------------------|--|---|---|--------------------------------------|--|---|---|--|---|
| 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER) | UNIT | 306 | 306 | | | | | | | | | | | |
| 20100210 | TREE REMOVAL (OVER 15 UNITS DIAMETER) | UNIT | 1237 | 1237 | | | | | | | | | | | |
| 20200100 | EARTH EXCAVATION | CU YD | 41965 | 41965 | | | | | | | | | | | |
| * 20200200 | ROCK EXCAVATION | CU YD | 300 | 100 | | | | | | | 100 | 100 | | | |
| 20800150 | TRENCH BACKFILL | CU YD | 15651 | 7914 | | | | | | | 7737 | | | | |
| * 21101625 | TOPSOIL FURNISH AND PLACE, 6" | SO YD | 36228 | | | | | | | | | | | 36228 | |
| * 25000110 | SEEDING, CLASS 1A | ACRE | 4 | | | | | | | | | | | 4 | |
| * 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 582 | | | | | | | | | | | 582 | |
| * 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 582 | | | | | | | | | | | 582 | |
| * 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 582 | | | | | | | | | | | 582 | |
| △ 25000750 | MOWING | ACRE | 4 | | | | | | | | | | 4 | | |
| * 25100125 | MULCH, METHOD 3 | ACRE | 7.25 | 7.25 | | | | | | | | | | | |
| * 25100630 | EROSION CONTROL BLANKET | SO YD | 229 | 229 | | | | | | | | | | | |
| * 25100900 | TURF REINFORCEMENT MAT | SO YD | 951 | 951 | | | | | | | | | | | |
| * 25200110 | SODDING, SALT TOLERANT | SO YD | 18500 | | | | | | | | | | | 18500 | |
| * 25200200 | SUPPLEMENTAL WATERING | UNIT | 925 | | | | | | | | | | | 925 | |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING | POUND | 7248 | 7248 | | | | | | | | | | | |
| 28000305 | TEMPORARY DITCH CHECKS | FOOT | 136 | 136 | | | | | | | | | | | |
| 28000400 | PERIMETER EROSION BARRIER | FOOT | 5414 | 5414 | | | | | | | | | | | |
| 28000500 | INLET AND PIPE PROTECTION | EACH | 32 | 32 | | | | | | | | | | | |
| 28000510 | INLET FILTERS | EACH | 231 | 231 | | | | | | | | | | | |
| 28001100 | TEMPORARY EROSION CONTROL BLANKET | SO YD | 1181 | 1181 | | | | | | | | | | | |
| 30300112 | AGGREGATE SUBGRADE IMPROVEMENT 12" | SO YD | 51152 | 51152 | | | | | | | | | | | |
| 30300115 | AGGREGATE SUBGRADE IMPROVEMENT 15" | SO YD | 1642 | 1642 | | | | | | | | | | | |
| 30300118 | AGGREGATE SUBGRADE IMPROVEMENT 18" | SO YD | 23081 | 23081 | | | | | | | | | | | |
| 30300121 | AGGREGATE SUBGRADE IMPROVEMENT 21" | SO YD | 124 | 124 | | | | | | | | | | | |
| 30300124 | AGGREGATE SUBGRADE IMPROVEMENT 24" | SO YD | 7363 | 7363 | | | | | | | | | | | |
| 30300127 | AGGREGATE SUBGRADE IMPROVEMENT 27" | SO YD | 556 | 556 | | | | | | | | | | | |

* SPECIALTY ITEM △ 100% STATE

| | | | | | | | | | | | | |
|---|----------------------|-------------|---------------------------|---|------------------------------|--------------|--------------------|-----------------|----------------------|------------------|------------------|-------------|
| FILE NAME: c:\pwwork\pwwork\hogan\jrd\0320875\0264821.sht-500.dgn | USER NAME: hogan\jrd | DESIGNED: - | REVISED: - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | | | F.A.P. RTE. 742 | SECTION (32, 33) R-1 | COUNTY WINNEBAGO | TOTAL SHEETS 705 | SHEET NO. 6 |
| PLOT SCALE: 2,0000' / 1" | CHECKED: - | REVISED: - | SCALE: | | SHEET NO. 1 OF 15 SHEETS | STA. TO STA. | CONTRACT NO. 64821 | | | | | |
| PLOT DATE: Thu Dec 13 12:00:36 2012 | DATE: - | REVISED: - | ILLINOIS FED. AID PROJECT | | | | | | | | | |
| | | | | | | | | | | | | |