

PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	80% FED	80% FED	80% FED	100% STATE	80% FED	80% FED	100% CITY	WATER MAIN	SAN SEWER	LANDSCAPE	LANDSCAPE	80% FED
				20% STATE ROADWAY 0004 URBAN	20% CITY BIKEPATH 0028 URBAN	20% STATE BRIDGE 0014 URBAN	HIGHWAY LIGHTING 0021 URBAN	20% STATE SPECIAL BRIDGE 0040 URBAN	10% CITY TRAFFIC SIGNALS 0021 URBAN	100% CITY TRAFFIC SIGNALS 0021 URBAN	100% STATE UTILITY 0043 URBAN	100% STATE UTILITY 0043 URBAN	100% STATE ROADWAY 0031 URBAN	80% STATE ROADWAY 0031 URBAN	20% STATE DEMOLITION 0044 URBAN
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SO YD	1735	1735											
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SO YD	4424		4424										
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SO YD	173	173											
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	14	5	9										
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	116	116											
40600990	TEMPORARY RAMP	SO YD	81	81											
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	207	207											
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	279	279											
40603415	HOT-MIX ASPHALT SURFACE COURSE, IL-9, 5FG, N50	TON	413		413										
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	223	223											
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SO YD	66656	66656											
42001200	PAVEMENT FABRIC	SO YD	507	507											
42001300	PROTECTIVE COAT	SO YD	67930	67930											
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SO YD	1274	1274											
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SO YD	6673	6673											
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	9240	86203	6245						32				
42400800	DETECTABLE WARNINGS	SO FT	1864	1157	707										
44000100	PAVEMENT REMOVAL	SO YD	63506	63506											
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	1214	1214											
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	4258	4258											
44000300	CURB REMOVAL	FOOT	1149	1149											
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	23991	23991											
44000600	SIDEWALK REMOVAL	SO FT	100122	100122											
44003100	MEDIAN REMOVAL	SO FT	318	318											
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1											
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1												
50102400	CONCRETE REMOVAL	CU YD	30		30										
50105220	PIPE CULVERT REMOVAL	FOOT	31	31											

\* SPECIALTY ITEM

FILE NAME : c:\pwwork\pwwork\hogsensord\40328075\064821-shr-500.dgn		USER NAME : Hogsensord	DESIGNED - DRAWN - CHECKED - DATE -	REVISED - REVISED - REVISED - REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>		<b>SUMMARY OF QUANTITIES</b>			F.A.P. RATE: 742	SECTION: (32, 33) R-1	COUNTY: WINNEBAGO	TOTAL SHEETS: 705	SHEET NO.: 7
PLOT SCALE : 2.0000 "/ IN. PLOT DATE : Thu Dec 13 12:00:36 2012					SCALE:			SHEET NO. 2 OF 15 SHEETS			STA. TO STA.			CONTRACT NO. 64821 ILLINOIS FED. AID PROJECT