

| PAY ITEM NUMBER | DESCRIPTION | UNIT | TOTAL QUANTITY | 80% FED 20% STATE ROADWAY 0004 URBAN | 80% FED 20% CITY BIKEPATH 0028 URBAN | 80% FED 20% STATE BRIDGE 0014 URBAN | 100% STATE HIGHWAY LIGHTING 0021 URBAN | 80% FED 20% STATE SPECIAL BRIDGE 0040 URBAN | 80% FED 10% STATE 10% CITY TRAFFIC SIGNALS 0021 URBAN | 100% CITY TRAFFIC SIGNALS 0021 URBAN | WATER MAIN UTILITY 0043 URBAN | SAN SEWER UTILITY 0043 URBAN | LANDSCAPE 100% STATE ROADWAY 0031 URBAN | LANDSCAPE 80% FED 20% STATE ROADWAY 0031 URBAN | 80% FED 20% STATE DEMOLITION 0044 URBAN |
|-----------------|------------------------------------|-------|----------------|--------------------------------------|--------------------------------------|-------------------------------------|--|---|---|--------------------------------------|-------------------------------|------------------------------|---|--|---|
| 50200100 | STRUCTURE EXCAVATION | CU YD | 135 | | | | | 135 | | | | | | | |
| 50300225 | CONCRETE STRUCTURES | CU YD | 225.4 | | 161.2 | | | 64.2 | | | | | | | |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 467.7 | | 229.5 | 238.2 | | | | | | | | | |
| 50300260 | BRIDGE DECK GROOVING | SQ YD | 499 | | 499 | | | | | | | | | | |
| 50300300 | PROTECTIVE COAT | SQ YD | 1455 | | 920 | 535 | | | | | | | | | |
| 50600200 | PAINTING STEEL RAILING | FOOT | 297 | | | 138 | | 159 | | | | | | | |
| 50800105 | REINFORCEMENT BARS | POUND | 660 | 660 | | | | | | | | | | | |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 152450 | | 82340 | 64750 | | 5360 | | | | | | | |
| 50800515 | BAR SPLICERS | EACH | 112 | | 112 | | | | | | | | | | |
| 50900805 | PEDESTRIAN RAILING | FOOT | 297 | | | 138 | | 159 | | | | | | | |
| 50901750 | PARAPET RAILING | FOOT | 291 | | 291 | | | | | | | | | | |
| 50901760 | PIPE HANDRAIL | FOOT | 307 | 307 | | | | | | | | | | | |
| 542D0217 | PIPE CULVERTS, CLASS D, TYPE 1 12" | FOOT | 150 | 150 | | | | | | | | | | | |
| 542D0220 | PIPE CULVERTS, CLASS D, TYPE 1 15" | FOOT | 26 | 26 | | | | | | | | | | | |
| 54215547 | METAL END SECTIONS 12" | EACH | 1 | 1 | | | | | | | | | | | |
| 54215550 | METAL END SECTIONS 15" | EACH | 2 | 2 | | | | | | | | | | | |
| 550A0050 | STORM SEWERS, CLASS A, TYPE 1 12" | FOOT | 353 | 353 | | | | | | | | | | | |
| 550A0070 | STORM SEWERS, CLASS A, TYPE 1 15" | FOOT | 20 | 20 | | | | | | | | | | | |
| 550A0120 | STORM SEWERS, CLASS A, TYPE 1 24" | FOOT | 149 | 149 | | | | | | | | | | | |
| 550A0180 | STORM SEWERS, CLASS A, TYPE 1 42" | FOOT | 124 | 124 | | | | | | | | | | | |
| 550A0340 | STORM SEWERS, CLASS A, TYPE 2 12" | FOOT | 4934 | 4934 | | | | | | | | | | | |
| 550A0360 | STORM SEWERS, CLASS A, TYPE 2 15" | FOOT | 2121 | 2121 | | | | | | | | | | | |
| 550A0380 | STORM SEWERS, CLASS A, TYPE 2 18" | FOOT | 1433 | 1433 | | | | | | | | | | | |
| 550A0410 | STORM SEWERS, CLASS A, TYPE 2 24" | FOOT | 1149 | 1149 | | | | | | | | | | | |
| 550A0430 | STORM SEWERS, CLASS A, TYPE 2 30" | FOOT | 132 | 132 | | | | | | | | | | | |
| 550A0450 | STORM SEWERS, CLASS A, TYPE 2 36" | FOOT | 51 | 51 | | | | | | | | | | | |
| 550A0470 | STORM SEWERS, CLASS A, TYPE 2 42" | FOOT | 150 | 150 | | | | | | | | | | | |
| 550A0660 | STORM SEWERS, CLASS A, TYPE 3 15" | FOOT | 269 | 269 | | | | | | | | | | | |

28
* SPECIALTY ITEM

| | | | | | | | | | | | | |
|---|------------------------|------------|-----------|---|--|--------------|-----------|--------------------|---------|--------|--------------|-----------|
| FILE NAME * | USER NAME * Hogensonjd | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | | | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| c:\pwork\pwork\hogensonjd\0328075\0328075.dgn | 64821-ah-500.dgn | DRAWN - | REVISED - | | 742 | (32, 33) R-1 | WINNEBAGO | 705 | 8 | | | |
| PLOT SCALE * 2.0000 "/ in. | CHECKED - | REVISED - | REVISED - | | SCALE: SHEET NO. 3 OF 15 SHEETS STA. TO STA. | | | CONTRACT NO. 64821 | | | | |
| PLOT DATE * Thu Dec 13 12:00:36 2012 | DATE - | REVISED - | REVISED - | | ILLINOIS FED. AID PROJECT | | | | | | | |