

PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	80% FED 20% STATE ROADWAY 0004 URBAN	80% FED 20% CITY BIKEPATH 0028 URBAN	80% FED 20% STATE BRIDGE 0014 URBAN	100% STATE HIGHWAY LIGHTING 0021 URBAN	80% FED 20% STATE SPECIAL BRIDGE 0040 URBAN	80% FED 10% STATE 10% CITY TRAFFIC SIGNALS 0021 URBAN	100% CITY TRAFFIC SIGNALS 0021 URBAN	WATER MAIN 100% STATE UTILITY 0043 URBAN	SAN SEWER 100% STATE UTILITY 0043 URBAN	LANDSCAPE 100% STATE ROADWAY 0031 URBAN	LANDSCAPE 80% FED 20% STATE ROADWAY 0031 URBAN	80% FED 20% STATE DEMOLITION 0044 URBAN
87703020	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 58 FT.	EACH	1						1						
87703050	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 64 FT.	EACH	1						1						
87703070	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 66 FT.	EACH	1						1						
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	52						52						
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	20						20						
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	74						74						
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	87						87						
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	88						88						
87900200	DRILL EXISTING HANDHOLE	EACH	1						1						
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4						4						
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	29						29						
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	5						5						
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	14						14						
88040230	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2						2						
88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	3						3						
88040290	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2						2						
88040330	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 2-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	1						1						
88102825	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	13						13						
88102845	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	9						9						
88102850	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, BRACKET MOUNTED	EACH	1						1						
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	43						43						
88600100	DETECTOR LOOP, TYPE I	FOOT	108						108						
88800100	PEDESTRIAN PUSH-BUTTON	EACH	31						31						
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	3						3						
89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	2							2					
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	5						5						
89502380	REMOVE EXISTING HANDHOLE	EACH	25	9					16						
89502382	REMOVE EXISTING DOUBLE HANDHOLE	EACH	4						4						

* SPECIALTY ITEM

FILE NAME *	USER NAME * Hognsonjd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\hognsonjd\0320075\0320075-001-500.dgn	DRAWN -	REVISED -	742		(32, 33) R-1	WINNEBAGO	705	15				
PLOT SCALE * 2,8800' / in.	CHECKED -	REVISED -	SCALE: SHEET NO. 10 OF 15 SHEETS STA. TO STA.			CONTRACT NO. 64821						
PLOT DATE * Thu Dec 13 12:00:39 2012	DATE -	REVISED -	ILLINOIS FED. AID PROJECT									