



PROPOSED TYPICAL SECTION - SIDESTREETS

LEGEND

- 1 PORTLAND CEMENT CONCRETE PAVEMENT, 9 1/2" (JOINTED)
- 2 AGGREGATE SUBGRADE IMPROVEMENT 12"
- 3 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24
- 4 TOPSOIL FURNISH AND PLACE, 6"
- 5 PORTLAND CEMENT CONCRETE SIDEWALK, 5"
- 6 EXISTING BIKE PATH
- 7 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12
- 8 TOPSOIL FURNISH AND PLACE, SPECIAL
- 9 EXISTING BRICK WALL
- 10 EXISTING ORNAMENTAL FENCE
- 11 1 1/2" HMA SURFACE COURSE MIX "C", N50
- 12 AGGREGATE SUBGRADE IMPROVEMENT
- 13 SEGMENTAL CONCRETE BLOCK WALL
- 14 CONCRETE MEDIAN SURFACE, 4 INCH
- 15 CORRUGATED MEDIAN
- 16 AGGREGATE SUBGRADE IMPROVEMENT 18"
- 17 PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"
- 18 AGGREGATE SUBGRADE IMPROVEMENT 24"
- 19 AGGREGATE FILL
- 20 2" HOT-MIX ASPHALT SURFACE COURSE IL-9.5FG N50
- 21 AGGREGATE BASE COURSE, TYPE B, 8"
- 22 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18
- 23 PIPE UNDERDRAINS 6"
- 24 2" INCIDENTAL HOT-MIX ASPHALT SURFACING
- 25 HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"
- 26 1" LEVELING BINDER (MACHINE METHOD), N50

NOTE:
HMA MIXTURE APPLICATION RATE = 112 LBS/SQ YD/IN

* GUTTER FLAG REVERSE PITCHED TO 2% AWAY FROM MEDIAN

NOTE:
GEOTECHNICAL REINFORCEMENT SHALL BE USED ON ALL SIDE STREETS
WHERE THE SUB-BASE GRANULAR MATERIAL IS GREATER THAN 12".

STREET	LOCATION		AGGREGATE SUBGRADE IMPROVEMENT THICKNESS	LT SIDEWALK WIDTH	LT PARKWAY WIDTH	LT LANE WIDTH	RT LANE WIDTH	RT PARKWAY WIDTH	RT SIDEWALK WIDTH
	FROM STA	TO STA							
POND ST	18+60	20+00	12"	5'	5'	12'	12'	0'	7'
BLACKHAWK AVE	28+30	30+00	12"	7'	0'	14'	12'	0'	7'
OGILBY AVE	38+90	40+00	12"	5'	VAR.	13'	13'	VAR.	5'
COLE AVE	48+85	50+00	12"	NA	VAR.	13'	13'	3'	5'
MICHIGAN AVE	68+90	69+50	12"	7'	0'	12'	12'	4'	5'
	69+50	70+00	24"						
INDIANA AVE	78+85	79+00	24"	5'	VAR.	12'	12'	VAR.	5'
	79+00	80+00	12"						
ILLINOIS AVE	88+85	89+50	24"	5'	12'	12.5'	12.5'	VAR.	5'
	89+50	90+00	12"						
ISLAND AVE	98+70	99+50	27"	5'	7'	16'	16'	9'	5' & VAR. (BLDG)
	99+50	100+00	12"						
HEATH ST	128+60	129+00	21"	5'	0'	11'	11'	0'	4'
	129+00	130+00	12"						
SALTER AVE	138+70	140+00	12"	5'	4'	15'	15'	4'	5'
LANE ST	150+00	151+80	12"	5'	10'	15'	15'	8'	5'
KNOWLTON ST (WEST LEG)	158+70	159+00	27"	5'	5'	15'	15'	3'	5'
	159+00	160+00	12"						
KNOWLTON ST (EAST LEG)	160+00	161+40	12"	5'	VAR.	13'	13'	10.5'	5'
LOOMIS ST (EAST LEG)	180+00	181+60	12"	5' & VAR. (BLDG)	10'	15'	15'	9'	5'
KENT ST	198+60	199+00	12"	6' & VAR. (BLDG)	7.5'	15.5'	15.5'	9.5'	5' & VAR. (BLDG)
	199+00	199+50	15"						
	199+50	200+00	12"						
ROCK ST	200+00	201+00	12"	NA	NA	17'	18'	VAR.	5'
RACE ST	220+00	220+70	12"	NA	NA	13'	13'	NA	NA