

**SANITARY SEWER SCHEDULE OF QUANTITIES**

**20200200 ROCK EXCAVATION**

CU YD	LOCATION	COMMENT
100	X	
100	TOTAL	

**X0320374 PLUG EXISTING SANITARY SEWERS**

EACH	LOCATION	COMMENT
1	377+20 45' LT	MH 021-008
1	TOTAL	

**X0322464 ABANDON AND FILL EXISTING SANITARY MANHOLE**

EACH	LOCATION	COMMENT
1	352+81 26' LT	MH 014-088
1	362+57 18' LT	MH 014-008
2	TOTAL	

**X0323760 SANITARY SEWER SERVICE, 6" PVC, COMPLETE**

NOTE: LOCATION = POINT OF CONNECTION AT MAIN

EACH	LOCATION	ADDRESS
1	159+20 10' RT	1323
1	352+83 20' RT	2431
1	375+25 9' RT	1913
1	379+80 6' LT	1817
1	382+23 21' LT	1719
1	395+19 7' RT	1429
1	395+82 7' RT	1425
1	404+38 10' RT	1225
8	TOTAL	

**X0324585 SANITARY SEWER SERVICE REMOVAL AND REPLACEMENT**

NOTE: LOCATION = POINT OF CONNECTION AT MAIN

EACH	LOCATION	ADDRESS
1	363+59 15' RT	2303
1	371+20 16' RT	2019 (To be paid for by C.O.R.)
1	374+83 12' RT	1917
1	378+90 8' LT	1821
1	382+00 21' LT	1721
1	382+68 19' LT	1717
1	393+91 7' LT	1437
1	394+41 7' RT	1435 (To be paid for by C.O.R.)
1	395+24 7' RT	1427
1	395+88 7' RT	1421
1	396+43 7' RT	1413 (To be paid for by C.O.R.)
1	399+99 7' RT	1321 (To be paid for by C.O.R.)
1	401+76 7' RT	1303 (To be paid for by C.O.R.)
1	403+08 10' RT	1232 (To be paid for by C.O.R.)
1	404+07 10' RT	1227 (To be paid for by C.O.R.)
1	404+60 10' RT	1223
1	404+95 11' RT	1215 (To be paid for by C.O.R.)
1	405+50 11.2' RT	1213 (To be paid for by C.O.R.)
1	409+48 13' RT	1115
1	413+97 18' LT	1009
20	TOTAL	

**X0326712 ABANDON AND FILL EXISTING SANITARY SEWER**

EACH	LOCATION	LOCATION	MANHOLE	MANHOLE
1	350+72 29' LT	TO 352+81 26' LT	014-047	TO 014-088
1	360+84 4' LT	TO 362+57 18' LT	014-007	TO 014-008
1	362+57 18' LT	TO 364+57 27' LT	014-008	TO 014-009
1	377+30 31' LT	TO 378+80 50' LT	021-008	TO
1	381+11 66' LT	TO 382+00 70' LT	021-003	TO 021-132
5	TOTAL			

**X6026051 SANITARY MANHOLES TO BE RECONSTRUCTED**

EACH	LOCATION	COMMENT
1	356+09 21' RT	MH 014-019
1	358+35 21' RT	MH 014-090
1	363+51 16' RT	MH 014-004
1	364+81 9' RT	MH 014-003
1	366+62 11' RT	MH 014-002
1	375+54 7' RT	MH 021-125
1	379+20 10' LT	MH 021-006
1	386+72 11' RT	MH 030-068
8	TOTAL	

**X6026054 SANITARY MANHOLES TO BE REMOVED**

EACH	LOCATION	COMMENT
1	360+84 4' LT	MH 014-007
1	364+57 27' LT	MH 014-009
1	373+41 30' LT	MH 021-024
1	377+30 31' LT	MH 021-008
1	381+11 66' LT	MH 021-003
1	382+00 70' LT	MH 021-132
1	383+17 65' LT	MH 021-004
1	385+02 19' LT	MH 032-069
1	388+85 6' RT	MH 030-006
1	389+24 6' RT	MH 030-105
1	389+34 29' RT	MH 030-005
1	390+95 7' RT	MH 030-007
1	392+98 7' RT	MH 030-008
1	397+69 7' RT	MH 030-009
1	398+47 6' RT	MH 030-080
1	402+59 10' RT	MH 032-057
1	407+88 13' RT	MH 032-040
1	411+20 19' LT	MH 032-019
1	411+21 13' RT	MH 032-018
1	414+71 18' LT	MH 032-017
1	415+17 12' LT	MH 032-004
1	424+30 21' RT	MH 034-003
22	TOTAL	

**X6026055 SANITARY MANHOLE, SPECIAL**

EACH	LOCATION	COMMENT	DIAMETER
1	364+48 61' LT	MH 1A	4'
1	373+41 30' LT	MH 021-024	4'
1	377+30 31' LT	MH 021-008	4'
1	381+11 66' LT	MH 021-003	4'
1	389+34 29' RT	MH 030-005	4'
1	397+69 7' RT	MH 030-009	4'
1	398+47 6' RT	MH 030-080	4'
1	402+59 10' RT	MH 032-057	4'
1	407+88 13' RT	MH 032-040	4'
1	414+71 18' LT	MH 032-017	4'
1	415+17 12' LT	MH 034-004	4'
1	385+02 19' LT	MH 032-069	5'
1	388+85 6' RT	MH 030-006	5'
1	389+24 6' RT	MH 030-105	5'
1	390+95 7' RT	MH 030-007	5'
1	392+98 7' RT	MH 030-008	5'
1	411+20 19' LT	MH 032-019	5'
1	411+21 13' RT	MH 032-018	5'
1	424+30 21' RT	MH 034-003	5'
19	TOTAL		

**X6026056 SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE I FRAME, CLOSED LID**

EACH	LOCATION	COMMENT
1	350+47 88' LT	MH 014-103 (To be paid for by IDOT)
1	350+72 29' RT	MH 014-047
1	350+93 20' RT	MH 014-044
1	353+86 20' RT	MH 014-043
1	360+30 19' RT	MH 014-148
1	361+02 19' RT	MH 014-006
1	362+60 22' RT	MH 014-005
1	368+37 11' RT	MH 014-001
1	371+03 14' RT	MH 021-023
1	373+65 19' RT	MH 021-126
1	377+30 0	MH 021-007
1	381+33 20' LT	MH 021-002
1	383+66 13' LT	MH 021-001
1	385+97 16' RT	MH 030-067
1	386+94 34' RT	MH 030-066
1	399+30 8' RT	MH 032-058
1	407+23 12' RT	MH 032-041 (To be paid for by IDOT)
1	417+20 28' RT	MH 032-001
1	420+92 22' RT	MH 034-001
1	428+30 21' RT	MH 034-004
1	433+66 21' RT	MH 034-014
1	121+08 7' RT	MH 030-104 (To be paid for by IDOT)
1	121+25 2' LT	MH 030-004 (To be paid for by IDOT)
1	171+58 2' RT	MH 030-070 (To be paid for by IDOT)
1	181+58	MH 030-078 (To be paid for by IDOT)
1	231+06	MH 034-172 (To be paid for by IDOT)
26	TOTAL	

**Z0056900 SANITARY SEWER, 8"**

FOOT	LOCATION	LOCATION
80.0	364+45 LT	TO 364+82 RT
80.0	TOTAL	

**Z0057000 SANITARY SEWER, 10"**

FOOT	LOCATION	LOCATION
36.0	360+80 LT	TO 361+03 RT
36.0	TOTAL	

**Z0062458 TEMPORARY PAVEMENT (VARIABLE DEPTH)**

TON	LOCATION	COMMENT
35	X	
35	TOTAL	

**Z0067700 STEEL CASING, 20"**

FOOT	LOCATION	LOCATION
160.0	350+45 75' LT	TO 351+03 75' RT
160.0	TOTAL	

**\*2000257 SANITARY SEWER MAINLINE REPAIR (10")**

FOOT	LOCATION	LOCATION	REPAIR NO.
26	199+60 11' RT	TO 199+74 11' RT	REPAIR NO. 5
	KENT ST.	KENT ST.	
26	TOTAL		

**\*2000258 SANITARY SEWER MAINLINE REPAIR (12")**

FOOT	LOCATION	LOCATION	REPAIR NO.
30	410+91 13' RT	TO 411+21 13' RT	REPAIR NO. 2
10	413+93 18' LT	TO 414+03 18' LT	REPAIR NO. 3
40	TOTAL		

**\*2000259 SANITARY SEWER MAINLINE REPAIR (15")**

FOOT	LOCATION	LOCATION	REPAIR NO.
20	374+86 11' RT	TO 374+92 11' RT	REPAIR NO. 1
25	415+05 13' RT	TO 415+17 12' LT	REPAIR NO. 4
45	TOTAL		