PAVEMENT REMOVAL INFORMATION

LOCATION			EXISTING PAVEMENT	SOURCE
	FROM	TO		
IL 2	STA 377+00	STA 411+00	3" ASPHALT ON 10" CONCRETE	OLD PLANS
KNOWLTON ST (WEST LEG)			5" ASPHALT	CORE
KNOWLTON ST (EAST LEG)			4" ASPHALT	CORE
MONTAGUE ST (WEST LEG)			6.5" ASPHALT ON 10.5" CONCRETE	CORE
MONTAGUE ST (EAST LEG)			3" ASPHALT	CORE

REMOVAL NOTES

1. SEE WATERMAIN PLANS FOR WATER ITEMS TO BE REMOVED OR ADJUSTED.
2. SEE SANITARY SEWER PLANS FOR SANITARY SEWER REMOVAL OR ADJUSTMENTS.
3. SEE TRAFFIC SIGNAL PLANS FOR REMOVAL OF EXISTING TRAFFIC SIGNAL EQUIPMENT.
4. SEE DISTRICT DETAIL 35.4, "SIDEWALK AND DRIVEWAY LIMITS OF DRIVEWAY AND SIDEWALK PAVEMENT PAY AREAS" FOR REMOVAL LIMITS.
5. BUILDING REMOVAL SHALL INCLUDE THE COMPLETE REMOVAL OF ALL FENCES, STEPS, PATIOS, GARAGES, SHEDS, ETC LOCATED ON THE PROPERTY THE BUILDING IS BEING REMOVED FROM, UNLESS NOTED OTHERWISE.
6. CHECK LANDSCAPING PLANS FOR TREES TO BE PROTECTED PRIOR TO BEGINING TREE REMOVAL. ANY TREES IDENTIFIED TO BE SAVED IN THE LANDSCAPING PLANS WHICH ARE MARKED TO BE REMOVED IN THE REMOVAL PLANS SHALL BE COORDINATED BY THE ENGINEER WITH THE CITY OF ROCKFORD.

REMOVAL LEGEND

- PAVEMENT REMOVAL
- SIDEWALK REMOVAL
- DRIVEWAY REMOVAL
- HMA SURFACE REMOVAL, 2 1/2"
- BUILDING REMOVAL
- PAVEMENT REMOVAL PAID FOR AS EARTH EXCAVATION (ASPHALT 6" OR LESS)
- APPROACH SLAB REMOVAL
- CONC MEDIAN SURF REMOVAL
- CORRUGATED MEDIAN REMOVAL
- MEDIAN REMOVAL
- COMBINATION CURB AND GUTTER REMOVAL
- CURB REMOVAL
- TREE REMOVAL, UNIT DIAMETER

PROJECT BEGINS STA 158+70.00
PROJECT ENDS STA 161+40.00
MATCH LINE 398+00
MATCH LINE 404+00
IL RTE 2 (S. MAIN ST.)
KNOWLTON ST
MONTAGUE STREET
158+84.04 35.27' LT
158+94.77 40.03' LT
168+73.88 33.17' RT
168+98.81 34.22' RT
168+96.25 44.90' RT
400+75.00 42.20' LT
400+44.92 41.15' LT
402+87.9 74.6 LT
403+16.5 48.7 LT
403+28.9 48.7 LT
CURB REM
FENCE REMOVAL
RETAINING WALL REMOV
COMB CURB GUTTER REM
RETAINING WALL REMOV & CONC STEP REMOV
ACCESS REMOVED
EX SIGN TO REMAIN
REM POLE FDN
EX LIGHT TO BE REMOVED BY OWNER
REM CONC FDN-GR MT
EX WALL TO BE CLEARED
SIGN

FILE NAME = $FILE$	USER NAME = $USER$	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = $SCALE$	CHECKED -	REVISED -
	PLOT DATE = $DATE$	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

REMOVAL PLANS
IL 2

SCALE: 1:20 | SHEET NO. 11 OF 23 SHEETS | STA. 398+00 TO STA. 404+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	(32, 33) R-1	WINNEBAGO	705	168
		CONTRACT NO. 64821		
	ILLINOIS FED. AID PROJECT			