

GENERAL NOTES:

1. THE LANDSCAPE PLANS CONTAINED HEREIN ILLUSTRATE APPROXIMATE LOCATIONS OF ALL EXISTING AND PROPOSED SITE CONDITIONS. REFER TO CIVIL ENGINEERING DRAWINGS FOR ADDITIONAL DETAILED INFORMATION.
2. THE CONTRACTOR SHALL VERIFY ALL SITE CONDITIONS. THE CONTRACTOR SHALL NOT WILLFULLY PROCEED WITH CONSTRUCTION AS DESIGNED WHEN IT IS APPARENT THAT UNKNOWN OBSTRUCTIONS AND/OR GRADE DIFFERENCES EXIST THAT MAY NOT HAVE BEEN KNOWN DURING DESIGN. SUCH CONDITIONS SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF IDOT AND THE CITY OF ROCKFORD FOR CLARIFICATION. THE CONTRACTOR SHALL ASSUME FULL RESPONSIBILITY FOR ALL LIABILITIES, INCLUDING NECESSARY REVISIONS DUE TO FAILURE TO GIVE SUCH NOTIFICATION.
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATION WITH SUBCONTRACTORS AND OTHER CONTRACTORS OF RELATED TRADES, AS REQUIRED, TO ACCOMPLISH THE PLANTING AND RELATED OPERATIONS.
4. MEDIANS WILL BE GRADED SO THAT ALL RAINFALL AND DRAINAGE IS CONTAINED AND COLLECTED WITHIN THE MEDIAN, WITH NO RUN-OFF OVER MEDIAN CURBS INTO THE ROADWAY.

GENERAL SEEDING AND SOD NOTES:

1. CONTRACTOR SHALL CONFORM TO GENERAL IDOT SPECIFICATIONS FOR THE INSTALLATION OF ALL TURF AREAS AND REFER TO SECTIONS 250, 251, AND 252 FOR ALL REQUIREMENTS.
2. FOR SEEDING AT ROCKFORD PARK DISTRICT PROPERTY, CONTRACTOR SHALL CONTACT THE CITY OF ROCKFORD AND THE ROCKFORD PARK DISTRICT OFFICIALS A MINIMUM OF TWO DAYS IN ADVANCE OF SEEDING TO OBTAIN APPROVAL. CONTACT JASON NEY, ROCKFORD PARK DISTRICT, 815-987-1649. SEE DRAWINGS FOR LOCATION.

GENERAL PLANTING NOTES:

1. THE CONTRACTOR SHALL COORDINATE INSTALLATION OF ALL PLANT MATERIAL WITH THE INSTALLATION OF OTHER IMPROVEMENTS SUCH AS HARDSCAPE ELEMENTS AND RELATED STRUCTURES. ANY DAMAGE TO EXISTING IMPROVEMENTS IS THE RESPONSIBILITY OF THE CONTRACTOR.
2. CONTRACTOR SHALL COORDINATE TREE PLANTING AND TRAFFIC CONTROL FOR TREES PLANTED IN THIS PROJECT WITH THE CONTRACTOR FROM THE SOUTHERN SOUTH MAIN, IL-2 PROJECT. CONTRACTOR WILL BE RESPONSIBLE FOR ALL TREES PLANTED ON THIS PROJECT AND TREES TO BE DELIVERED AND PLANTED AT OTHER ROCKFORD LOCATIONS. CONTRACTOR WILL COORDINATE THESE OPERATIONS WITH THE CITY OF ROCKFORD AND THE ENGINEER.
3. THE CONTRACTOR IS RESPONSIBLE TO RESTORE ALL AREAS OF THE SITE, OR ADJACENT AREAS, WHERE DISTURBED BY OPERATIONS OF OR RELATED TO THE CONTRACTOR'S WORK.
4. CONTRACTOR MUST INCLUDE LIST OF NURSERY SOURCES FOR ALL SPECIFIED PLANT MATERIAL TO THE IDOT ENGINEER AND THE CITY OF ROCKFORD PRIOR TO OBTAINING MATERIALS SECURING ORDER.
5. NO SUBSTITUTIONS OF PLANT MATERIAL, QUANTITIES OR SIZES WILL BE PERMITTED WITHOUT APPROVAL BY THE IDOT ENGINEER AND THE CITY OF ROCKFORD.
6. FINAL LOCATION AND STAKING OF ALL PLANT MATERIALS SHALL BE ACCEPTED BY THE IDOT ENGINEER AND THE CITY OF ROCKFORD IN ADVANCE OF PLANTING PER ARTICLE 253.07.
7. ALL CORDS AND BURLAP SHALL BE REMOVED FROM THE TREE TRUNKS DURING PLANTING. CONTRACTOR SHALL COORDINATE WITH IDOT AND THE CITY TO INSPECT TREE PITS PRIOR TO BACKFILLING, TO INSURE WIRE BASKETS ARE PROPERLY REMOVED FROM THE UPPER ONE HALF OF PLANTING BULB PER ARTICLE 253.10
8. PRIOR TO BEING ACCEPTED, ALL PLANTS SHALL ENDURE A PERIOD OF ESTABLISHMENT AS DEFINED IN ARTICLE 253.14
9. PLANT CARE:
THE CONTRACTOR SHALL REFER TO ARTICLE 253.15 FOR ALL PLANT CARE REQUIREMENTS DURING THE PERIOD OF ESTABLISHMENT.
10. INSTALLATION PROTECTION:
THE CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF NEW PLANTING FROM CONSTRUCTION TRAFFIC.
11. TOPSOIL PLACEMENT:
THE CONTRACTOR SHALL REFER TO SECTION 211 FOR ALL TOPSOIL REQUIREMENTS.

SUMMARY OF QUANTITIES

ITEM NUMBER	ITEMS	UNIT	QUANTITY
21101625	TOPSOIL FURNISH AND PLACE, 6"	SO YD	37,480
25000110	SEEDING, CLASS 1A	ACRE	4
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	582
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	582
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	582
25000750	MOWING	ACRE	4
25200110	SODDING, SALT TOLERANT	SO YD	18,500
25200200	SUPPLEMENTAL WATERING	UNIT	925
A2007230	TREE, ROBINIA PSEUDOACACIA BENJAMIN (BENJAMIN BLACK LOCUST), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	11
A2008819	TREE, ULMUS AMERICANA VALLEY FORGE (VALLEY FORGE AMERICAN ELM), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	13
B2000770	TREE, AMELANCHIER X GRANDIFLORA AUTUMN BRILLIANCE (AUTUMN BRILLIANCE SERVICE BERRY), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	21
B2002268	TREE, CRATAEGUS VIRIDIS WINTER KING (WINTER KING GREEN HAWTHORN), 7' HEIGHT CLUMP FORM, BALLED AND BURLAPPED	EACH	19
B2005014	TREE, MALUS SNOWDRIFT (SNOWDRIFT CRABAPPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	16
B2006270	TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 8' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	19
B2007066	TREE, MALUS PURPLE PRINCE (PURPLE PRINCE CRABAPPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	14
* X2010507	CLEARING, SPECIAL	ACRE	1
** XX007908	COLORLED SURFACE	SO FT	3,318
* 2000274	PORTLAND CEMENT CONCRETE ACCENT STRIP	SO FT	2,072
** 2000276	MEDIAN INLET, SPECIAL	EACH	25

† SPECIALTY ITEM
* SPECIAL PROVISION

COMPANY NAME: HRGreen
PROJECT CONTACT: Dave Reitz
DATE PLOTTED: 11/28/2012 9:38:44 AM
FILE NAME: 0264821-shr+landscape-gen.dgn
PLOT DRIVER: pdfcut
PEN TABLE: standard-trans.tbl



USER NAME = whood	DESIGNED - DLR	REVISED -
	DRAWN - WJH	REVISED -
PLOT SCALE =	CHECKED - DVC	REVISED -
PLOT DATE = 11/28/2012	DATE - 11/28/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL RTE 2 LANDSCAPE PLANS
GENERAL NOTES**

SCALE: 1"=20' SHEET 1 OF 21 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	(32, 33) R-1	WINNEBAGO	705	279
CONTRACT NO.				
ILLINOIS FED. AID PROJECT				