



MATCH LINE STA. 375+00.00

MATCH LINE STA. 380+00.00

DRAINAGE SYSTEM QUANTITIES (SEE DETAILS)

4	-	IN-LINE DRAIN INLET
4	-	TEES
4	-	20" RISERS

NOTE:
ALL MEDIANS WILL BE GRADED SO THAT ALL RAINFALL AND DRAINAGE IS CONTAINED AND COLLECTED WITHIN THE MEDIAN, WITH NO RUN-OFF OVER MEDIAN CURBS ONTO THE ROADWAY.

CONTRACTOR TO COMPLETE SELECTIVE CLEARING AND PRUNING IN THE TREE GROVE BETWEEN BIKE TRAIL AND THE ROCK RIVER SHORELINE. UNDESIRABLE SPECIES AND UNDERBRUSH SHALL BE REMOVED. ALL TREES TAGGED FOR PRESERVATION SHALL BE "LIMBED-UP" AND PRUNED TO A MINIMUM HEIGHT OF 8'-0". CONTRACTOR SHALL COORDINATE SELECTIVE CLEARING WORK WITH THE CITY ENGINEER AND THE CITY ARBORIST. ALL DEAD LIMBS AND FALLEN TREE DEBRIS WILL ALSO BE REMOVED. THE INTENT OF THE SELECTIVE CLEARING WORK IS TO SEE THE RIVER FROM THE BIKE PATH. PAID FOR AS CLEARING SPECIAL. 0.2 ACRES

LEGEND

	COLORED SURFACE		SODDING, SALT TOLERANT
	PCC ACCENT STRIP		SEEDING, CLASS 1A

COMPANY NAME: Dave Rife
 PROJECT CONTACT: Dave Rife
 DATE PLOTTED: 11/19/2012 5:06:55 PM
 FILE NAME: 0264821-snh+indiana-il_2-375.dgn
 PLOT DRIVER: pdf.plt, no_levelplot.ctb
 PEN TABLE: standard-trans.tbl



USER NAME = whood	DESIGNED - DLR	REVISED -
	DRAWN - WJH	REVISED -
PLOT SCALE =	CHECKED - DVC	REVISED -
PLOT DATE = 11/19/2012	DATE - 11/19/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

IL RTE 2 LANDSCAPE PLANS

SCALE: 1"=20' SHEET 8 OF 21 SHEETS STA. 375+00 TO STA. 380+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	(32, 33) R-1	WINNEBAGO	705	286
CONTRACT NO.				

NOTES:
SEE PLAN AND PROFILE SHEETS FOR CONSTRUCTION LAYOUT AND ADDITIONAL INFORMATION

