

PLANT SCHEDULE									
TREES FROM NORTHERN SOUTH MAIN CONTRACT									
(POND ST. TO CEDAR ST.)									
CODE NO.	QTY SHOWN ON PLAN	OFFSITE PLANTINGS	TOTAL PLAN QTY	KEY	BOTANICAL NAME/ITEM	COMMON NAME	SIZE	COND	REMARKS
CANOPY TREES									
A2007230	11	0	11	BBL	ROBINIA PSEUDOACACIA BENJAMIN	BENJAMIN BLACK LOCUST	2.5" CAL.	B&B	THORNLESS ONLY
A2008819	9	4	13	VAE	ULMUS AMERICANA VALLEY FORGE	VALLEY FORGE AMERICAN ELM	2.5" CAL.	B&B	
ORNAMENTAL TREES									
B2000770	16	5	21	ABS	AMELANCHIER X GRANDIFLORA AUTUMN BRILLIANCE	AUTUMN BRILLIANCE SERVICE BERRY	2" CAL.	B&B	
B2002268	16	3	19	WKH	CRATAEGUS VIRDIS WINTER KING	WINTER KING GREEN HAWTHORN	7' HEIGHT	B&B	CLUMP FORM
B2005014	13	3	16	SC	MALUS SNOWDRIFT	SNOWDRIFT CRABAPPLE	1.75" CAL.	B&B	FRUITLESS ONLY
B2006270	16	3	19	JTL	SYRINGA RETICULATA	JAPANESE TREE LILAC	8' HEIGHT	B&B	CLUMP FORM
B2007066	11	3	14	PPC	MALUS PURPLE PRINCE	PURPLE PRINCE CRABAPPLE	2" CAL.	B&B	
TOTALS									
	92	21	113						

PLANT SCHEDULE									
TREES FROM SOUTHERN SOUTH MAIN CONTRACT									
(BELTLINE ROAD TO CLIFTON AVE.)									
CODE NO.	QTY SHOWN ON PLAN	OFFSITE PLANTINGS	TOTAL PLAN QTY	KEY	BOTANICAL NAME/ITEM	COMMON NAME	SIZE	COND	REMARKS
CANOPY TREES									
A2000224	7	5	12	MFM	ACER X FREEMAN II MARMO	MARMO FREEMAN MAPLE	3" CAL.	B&B	
A2002824	8	5	13	C	CATALPA SPECIOSA	NORTHERN CATALPA	3" CAL.	B&B	
A2005020	8	6	14	KC	GYMNOCLADUS DIOICUS	KENTUCKY COFFEETREE	2.5" CAL.	B&B	
A2005424	11	6	17	TT	LIRIODENDRON TULIPIFERA	TULIP TREE	3" CAL.	B&B	
A2005824	10	7	17	S	PLATANUS OCCIDENTALIS	SYCAMORE	3" CAL.	B&B	
A2006520	11	9	20	SWO	QUERCUS BICOLOR	SWAMP WHITE OAK	2.5" CAL.	B&B	
A2006618	13	9	22	SO	QUERCUS IMBRICARIA	SHINGLE OAK	2.5" CAL.	B&B	
A2006726	12	8	20	BO	QUERCUS MACROCARPA	BUR OAK	3" CAL.	B&B	
A2006820	10	6	16	CO	QUERCUS MUEHLENBERGII	CHINKAPIN OAK	2.5" CAL.	B&B	
A2007116	10	5	15	RO	QUERCUS RUBRA	RED OAK	2" CAL.	B&B	
A2007724	10	5	15	SBC	TAXODIUM DISTICHUM SHAWNEE BRAVE	SHAWNEE BRAVE BALD CYPRESS	3" CAL.	B&B	
A2007824	14	5	19	AL	TILIA AMERICANA	AMERICAN LINDEN/BASSWOOD	3" CAL.	B&B	
A2008519	17	8	25	TE	ULMUS MORTON GLOSSY	TRIUMPH ELM	2.5" CAL.	B&B	
ORNAMENTAL TREES									
A2002562	0	7	7	AH	CARPINUS CAROLINIANA	AMERICAN HORNBEAM	4' HEIGHT	B&B	
B2001116	9	5	14	ER	CERCIS CANADENSIS	EASTERN REDBUD	2" CAL.	B&B	
B2001266	14	5	19	PD	CORNUS ALTERNIFOLIA	PAGODA DOG WOOD	6' HEIGHT	B&B	CLUMP FORM
B2004166	10	3	13	PC	MALUS PRAIRIFIRE	PRAIRIEFIRE CRABAPPLE	6' HEIGHT	B&B	CLUMP FORM
SHRUBS									
C2000636	0	9	9	BC	ARONIA MELANOCARPA ELATA	GLOSSY BLACK CHOKEBERRY	3' HEIGHT	B&B	
TOTALS									
	174	113	287						

GENERAL NOTES:

- THE COLUMN LABELED "QTY SHOWN ON PLANS" ARE PLANTINGS THAT ARE SPECIFICALLY DETAILED IN THESE PLANS WITH LOCATIONS. THE COLUMN LABELED "OFFSITE PLANTINGS" REFERS TO TREES AND SHRUBS THAT SHALL BE PLANTED IN OTHER ROCKFORD LOCATIONS BASED ON INFORMATION PROVIDED BY THE CITY OR THE ENGINEER. COORDINATE DELIVERY AND PLANTING WITH THE CITY OF ROCKFORD. THE "TOTAL PLAN QTY" COLUMN REFERS TO THE NUMBER OF TREES AND SHRUBS TO BE PLANTED PER THE CONTRACT.
- CONTRACTOR SHALL COORDINATE THE TREE PLANTINGS AND THE TRAFFIC CONTROL FOR TREES PLANTED IN THIS PROJECT WITH THE CONTRACTOR FROM THE SOUTHERN SOUTH MAIN, IL-2 PROJECT. CONTRACTOR WILL BE RESPONSIBLE FOR ALL TREES USED ON THE PLANT SCHEDULE - BOTH PLANTED TREES AND THOSE TREES THAT WILL BE DELIVERED AND PLANTED IN OTHER ROCKFORD LOCATIONS.

COMPANY NAME: HRGreen
 PROJECT CONTACT: Dave Reitz
 DATE PLOTTED: 11/21/2012 9:40:34 AM
 FILE NAME: 0264821-sh+landscape-01.dgn
 PLOT DRIVER: pdfcut
 PEN TABLE: standard-trans.tbl



USER NAME = whood	DESIGNED - DLR	REVISED -
	DRAWN - WJH	REVISED -
PLOT SCALE =	CHECKED - DVC	REVISED -
PLOT DATE = 11/21/2012	DATE - 11/21/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

IL RTE 2 LANDSCAPE PLANS

SCALE: SHEET 19 OF 21 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	(32, 33) R-1	WINNEBAGO	705	297
CONTRACT NO.				
ILLINOIS FED. AID PROJECT				