

TRAFFIC SIGNAL SUMMARY OF QUANTITIES

CODE #	ITEM	UNIT	TOTAL QUANTITY	IL RTE 2/ MARCHESANO/15TH 80% FED 10% STATE 10% CITY	IL RTE 2/ FIRE DEPARTMENT 100% CITY	IL RTE 2/ MONTAGUE ST 80% FED 10% STATE 10% CITY	IL RTE 2/ MORGAN ST 80% FED 10% STATE 10% CITY	IL RTE 2/ CEDAR ST 80% FED 10% STATE 10% CITY	CEDAR ST/ CHURCH ST 80% FED 10% STATE 10% CITY
87702960	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 46 FT.	EACH	1			1			
87702990	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 54 FT.	EACH	1				1		
87703010	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 56 FT.	EACH	1				1		
87703020	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 58 FT.	EACH	1	1					
87703050	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 64 FT.	EACH	1			1			
87703070	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 66 FT.	EACH	1				1		
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	52	12	8	8	12	12	
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	20	4	4	4	4	4	
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	74	13.5	10	13.5	14	24	
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	87	24	11	26	15	11	
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	88	21		21	46		
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4		2			2	
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	29	7	4	6	6	6	
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	5			3	2		
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	14	4		4	6		
88040230	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2		1			1	
88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	3	3					
88040290	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2				2		
88040330	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 2-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	1	1					
88102825	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	13	4	2	2	2	3	
88102845	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	9	2		2	3	2	
88102850	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, BRACKET MOUNTED	EACH	1					1	
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	43	11	4	10	12	6	
88600100	DETECTOR LOOP, TYPE I	FOOT	108						108
88800100	PEDESTRIAN PUSH-BUTTON	EACH	31	6	2	8	8	7	
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	3	1	1	1			
89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	2		2				
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	5	1	1	1	1	1	
89502380	REMOVE EXISTING HANDHOLE	EACH	16	4		4	3	5	
89502382	REMOVE EXISTING DOUBLE HANDHOLE	EACH	4	2		1	1		
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	29	7	4	5	8	5	
X0324102	EMERGENCY VEHICLE SIGNAL CONTROL SYSTEM	EACH	4	1		1	1	1	
X8210677	LUMINAIRE, PULSE START, METAL HALIDE, HORIZONTAL MOUNT 400 WATT (SPECIAL)	EACH	13	4		4	4	1	
Z0033072	VIDEO VEHICLE DETECTION SYSTEM	EACH	4	1		1	1	1	
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	3	1		1			1

• - 100% CITY

FILE NAME =	USER NAME = Hogensonjd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>TRAFFIC SIGNAL S00</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pw\work\p\dot\hogensonjd\0328875\064821-sh-t-TS-S00.dgn	DRAWN -	REVISED -	742			(32, 33) R-1	WINNEBAGO	705	432	
PLOT SCALE = 2.0000' / in.	CHECKED -	REVISED -	CONTRACT NO. 64821							
PLOT DATE = Thu Dec 13 12:02:37 2012	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
				SCALE:	SHEET NO. 2 OF 24 SHEETS	STA.	TO STA.			