



- LEGEND**
- EXISTING ROADWAY LIGHTPOLE AND LUMINAIRE TO BE REMOVED, SALVAGE
  - PROPOSED DECORATIVE LIGHT POLE AND LUMINAIRE ALUMINUM, 40 FT. M.H., PULSE START METAL HALIDE, HORIZONTAL MOUNT 400 WATT (SEE NOTE 13 ON SHEET 487)
  - PROPOSED UNDERPASS LUMINAIRE, METAL HALIDE, VERTICAL MOUNT, 100 WATT
  - ◆ PROPOSED UTILITY POLE (BY OTHERS)
  - PROPOSED LIGHTING CONTROLLER, 100 AMP, 480V
  - HH = PROPOSED HANDHOLE PER IDOT STD 814001 CHH = PROPOSED HANDHOLE, COMPOSITE CONCRETE TYPE AS INDICATED
  - PROPOSED JUNCTION BOX
  - ▬ PROPOSED CONDUIT ATTACHED TO STRUCTURE, SIZE AND CONDUCTORS AS INDICATED
  - ▬ PROPOSED UNDERGROUND CONDUIT, GALVANIZED STEEL, BORED AND PULLED, SIZE AND CONDUCTORS AS INDICATED.
  - ▬ L PROPOSED UNIT DUCT, 600V, 2-1/C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1/4" DIA. POLYETHYLENE
  - ▬ FO PROPOSED UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2" DIA. WITH PULL STRING AND TRACER CABLE
  - ▬ PROPOSED UNDERGROUND CONDUIT, GALVANIZED STEEL, SIZE AND CONDUCTORS AS INDICATED

- NOTES:**
- REFER TO ROADWAY LIGHTING NOTES ON SHEET 487.

MODEL NAME = Default	DESIGNED - JWD	REVISED -
FILE NAME = D264821-eh-light1106.dgn	DRAWN - JWD	REVISED -
PLOT SCALE = 40.0000' / 1"	CHECKED - AB	REVISED -
PLOT DATE = 11/20/2012 - 11:27:52 AM	DATE - 11/02/2012	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**ROADWAY LIGHTING PLAN  
IL RTE 2 (SOUTH MAIN STREET)**

SCALE: 1" = 20' SHEET 6 OF 32 SHEETS STA. 369+00 TO STA. 375+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	(32, 33) R-1	WINNEBAGO	705	492
CONTRACT NO. 64821			ILLINOIS FED. AID PROJECT	

DIRECTORY = I:\ROCKFORD\118004\Draw\CADD\_Sheets\DR4821.DWG  
 USER NAME = Jansen Dove  
 CMT CRAWFORD, MURPHY & TILLY, INC. CONSULTING ENGINEERS License No. 184-0206913