



LEGEND

	EXISTING ROADWAY LIGHTPOLE AND LUMINAIRE TO BE REMOVED, SALVAGE		PROPOSED UTILITY POLE (BY OTHERS)
	PROPOSED DECORATIVE LIGHT POLE AND LUMINAIRE ALUMINUM, 40 FT. M.H., PULSE START METAL HALIDE, HORIZONTAL MOUNT 400 WATT (SEE NOTE 13 ON SHEET 487)		PROPOSED LIGHTING CONTROLLER, 100 AMP, 480V
	PROPOSED UNDERPASS LUMINAIRE, METAL HALIDE, VERTICAL MOUNT, 100 WATT		HH = PROPOSED HANDHOLE PER IDOT STD 814001 CHH = PROPOSED HANDHOLE, COMPOSITE CONCRETE TYPE AS INDICATED
			PROPOSED JUNCTION BOX
			PROPOSED CONDUIT ATTACHED TO STRUCTURE, SIZE AND CONDUCTORS AS INDICATED

	PROPOSED UNDERGROUND CONDUIT, GALVANIZED STEEL, BORED AND PULLED, SIZE AND CONDUCTORS AS INDICATED.
	PROPOSED UNIT DUCT, 600V, 2-1/C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE
	PROPOSED UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2" DIA. WITH PULL STRING AND TRACER CABLE
	PROPOSED UNDERGROUND CONDUIT, GALVANIZED STEEL, SIZE AND CONDUCTORS AS INDICATED

NOTES:

1. REFER TO ROADWAY LIGHTING NOTES ON SHEET 487.



MODEL NAME = Default	DESIGNED - JWD	REVISED -
FILE NAME = D264821-shl-hght115.dgn	DRAWN - JWD	REVISED -
PLOT SCALE = 40.0000' / in.	CHECKED - AB	REVISED -
PLOT DATE = 11/20/2012 - 11:28:38 AM	DATE - 11/02/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**ROADWAY LIGHTING PLAN
IL RTE 2 (SOUTH MAIN STREET)**

SCALE: 1" = 20' SHEET 15 OF 32 SHEETS STA. 422+00 TO STA. 428+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	(32, 33) R-1	WINNEBAGO	705	501
CONTRACT NO. 64821				

ILLINOIS FED. AID PROJECT

DIRECTORY = I:\ROCKFORD\112804\Draw\CADD_Sheets\DR4821_DJA.dwg
 USER NAME = Jensen Dove