

SUMMARY OF QUANTITIES

GENERAL NOTES

Pay Item Number	Description	Units	Total Quantity
50901720	BICYCLE RAILING	FOOT	600
50901750	PARAPET RAILING	FOOT	600
67100100	MOBILIZATION	L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701806	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1

URBAN
100 % STATE
0014

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123.

All Borrow/Waste/Use sites must be approved by the Department prior to removing any material from the project or initiating any earth moving activities, including temporary stockpiling outside the limits of construction.

The cost of the removal of existing bicycle railing and parapet railing is included in the pay item BICYCLE RAILING AND PARAPET RAILING.

5