

URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE	BRIDGE
				0004	0011	0011
					EX S. N. 053-0159	EX S. N. 053-0070
28000500	INLET AND PIPE PROTECTION	EACH	5	5		
28100105	STONE RIPRAP, CLASS A3	SQ YD	56	56		
28100107	STONE RIPRAP, CLASS A4	SQ YD	1489		832	657
28200200	FILTER FABRIC	SQ YD	1545	56	832	657
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	106	106		
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	654	654		
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	183	183		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	58	58		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	100	100		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	789	789		
40600300	AGGREGATE (PRIME COAT)	TON	13	13		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	1.2	1.2		
40600525	LEVELING BINDER (HAND METHOD), N50	TON	2.3	2.3		
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	527	527		

14

FILE NAME	USER NAME - Schwanik.org	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
66832	66832	DRAWN	REVISED			681	013 BRBR & 013 BR-1BR	LIVINGSTON	123	4
11/01/2012	11/01/2012	CHECKED	REVISED			CONTRACT NO. 66832				
11/01/2012	11/01/2012	DATE	REVISED			ILLINOIS FED. AID PROJECT				
SCALE:		SHEET OF SHEETS		STA. TO STA.						