URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				ROADWAY 0004	BRIDGE 0011 EX S. N. 053-0159	BRIDGE 0011 EX S. N. 053-0070
50200300	COFFERDAM EXCAVATION	CU YD	208			208
50201101	COFFERDAM (TYPE 1) (LOCATION - 1)	EACH	1			1
50201102	COFFERDAM (TYPE 1) (LOCATION - 2)	EACH	1			1
50300100	FLOOR DRAINS	EACH	3			3
50300225	CONCRETE STRUCTURES	CU YD	213.5		55.1	158.4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	504		230.8	273.2
50300260	BRIDGE DECK GROOVING	SQ YD	1023		496	527
50300265	SEAL COAT CONCRETE	CU YD	113			113
50300280	CONCRETE ENCASEMENT	CU YD	9.8		4.2	5.6
50300300	PROTECTIVE COAT	SQ YD	1240		614	626
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	
50500505	STUD SHEAR CONNECTORS	EACH	1134		1134	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	146,070		57,680	88,390
50800515	BAR SPLICERS	EACH	562		562	

19

Rev.

FILE NAME:	USER NAME = Schwenberg	DESIGNED -	REVISED -
	66832-sht-503-dgn	DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 12/13/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
681	013 BR(BR & 013 BR-1)(BR	LIVINGSTON	123	6
		CONTRACT NO. 66832		
		ILLINOIS FED. AID PROJECT		