

GUARDRAIL SCHEDULE

STATION	STATION	LOCATION	SPBGR TY A 6FT POSTS	TRAF BAR TERM T6	TR BAR TRM T1 SPL TAN	TR BAR TRM T1 SPL FLR	GUARDRAIL REMOVAL	GUARDRAIL MKR TYPE A	BAR WALL MKR TYPE A	TERMINAL MARKER - DA
			63000001 (FOOT)	63100085 (EACH)	63100167 (EACH)	63100169 (EACH)	63200310 (FOOT)	78200410 (EACH)	78200510 (EACH)	78201000 (EACH)
23+35	24+63	SW QUAD					128			
23+48.1	23+98.1	NW QUAD			1			1		1
23+48.3	23+98.1	SW QUAD				1		1		1
23+72	24+63	NW QUAD					91			
23+98.1	24+41.3	NW QUAD		1				1		
23+98.1	24+41.3	SW QUAD		1				1		
24+41.3	25+41.8	WB							2	
24+41.3	25+41.8	EB							2	
25+20	25+98	SE QUAD					78			
25+20	26+61	NE QUAD					141			
25+41.8	25+84.9	SE QUAD		1				1		
25+41.8	25+84.9	NE QUAD		1				1		
25+84.9	26+34.7	SE QUAD			1			1		1
25+84.9	26+97.4	NE QUAD	112.5					1		1
26+97.4	27+47.4	NE QUAD			1			1		1
TOTAL			112.5	4	3	1	438	9	4	4

SEEDING SCHEDULE

STATION	STATION	OFFSET	SEEDING CL 2A 25000210 (ACRE)	NITROGEN FERT NUTR 25000400 (POUND)	PHOSPHORUS FERT NUTR 25000500 (POUND)	POTASSIUM FERT NUTR 25000600 (POUND)	EROS CONTR BLANKET 25100630 (SQ YD)	TEMP EROS CONTR SEED 28000250 (POUND)
21+20	24+56	LT	0.20	18	18	18	875	60
21+20	24+56	RT	0.10	9	9	9	400	30
25+27	29+05	LT	0.20	18	18	18	750	60
25+27	29+05	RT	0.25	23	23	23	950	75
TOTAL			0.75	68	68	68	2,975	225

TRAFFIC CONTROL ITEMS

STATION	STATION	OFFSET	SHORT TERM PAVT MKING	TEMP PVT MK LINE 4	TEMP PVT MK LINE 24	WORK ZONE PAVT MK REM	TEMP CONC BARRIER	REL TEMP CONC BARRIER	IMP ATTN TEMP NRD TL3	IMP ATTN REL NRD TL3
			70300100 (FOOT)	70300220 (FOOT)	70300280 (FOOT)	70301000 (SQ FT)	70400100 (FOOT)	70400200 (FOOT)	Z0030250 (EACH)	Z0030350 (EACH)
STAGE 1										
21+22	21+22	RT			28	56				
21+35	28+42	RT		705		235				
22+75	27+33	LT		455		152				
23+59	27+10						350			
23+59		CL							1	
27+10		4' RT							1	
29+02	29+02	LT			28	56				
STAGE 2										
21+20	29+05	RT	240			27				
21+20	29+05	LT	240			27				
21+20	29+05	CL	240			27				
21+82	28+91	LT		710		237				
22+50	27+90	RT		540		180				
22+99	27+22						75	350		
22+99		4' LT								1
27+22		4' LT								1
TOTAL			720	2,410	56	997	425	350	2	2

TREE REMOVAL SCHEDULE

STATION	STATION	OFFSET	TREE REMOV 6-15 20100110 (UNIT)	TREE REMOV OVER 15 20100210 (UNIT)
24+00	24+80	RT	94	77
25+00	25+75	RT	43	30
TOTAL			137	107

EARTHWORK SCHEDULE

STATION	STATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (NOTE 1)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		20200100 (CU YD)	(CU YD)	(CU YD)	(CU YD)
21+00	29+05	505	380	465	-85
AT STRUCTURE (NOTE 2)		303	227		227
TOTAL		808	607	465	142

EARTHWORK NOTES:

- ESTIMATED SHRINKAGE FACTOR = 25%.
- THE ENGINEER SHALL DETERMINE IF EXCAVATION IS SUITABLE FOR USE AS FILL MATERIAL.