

PAVEMENT MARKING												
LOCATION	TEMPORARY PAVEMENT MARKING- LINE 4"		TEMPORARY PAVEMENT MARKING- LINE 24"	PAINT PAVEMENT MARKING LINE 4"		PAINT PAVEMENT MARKING LINE 8"	PAINT PAVEMENT MARKING LINE 12"	PAINT PAVEMENT MARKING LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
	WHITE	YELLOW	FOOT	WHITE	YELLOW	FOOT	FOOT	FOOT	EACH	EACH	SQ FT	EACH
	FOOT	FOOT		FOOT	FOOT							
IL 116				1952	1972				2	1		2
CR 24	221	601	42	1280	1552	288	240	46			40	
N1750 E	197	549	12	2018	200			46			30	
TOTALS	418	1150	54	5250	3724	288	240	92	2	1	70	2

TEMPORARY PAVEMENT MARKINGS QUANTITIES APPLY TO THE DETOUR.

PAINT PAVEMENT MARKING QUANTITIES ARE FOR TWO APPLICATIONS

EARTHWORK				
LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (NOTE 1)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
IL 116 WEST OF S.N. 053-0070 (EX) /S.N. 053-0191 (PR)	23.1	17.3	124.6	-107.3
EAST OF S.N. 053-0070 (EX) /S.N. 053-0191 (PR)	68.4	51.3	185.2	-133.9
CR 24	20.8	19.1	15.8	3.3
N1750 E NORTH OF S.N. 053-3450	5.8	0.3	0.2	0.1
SOUTH OF S.N. 053-3450	0	0	0.0	0.0
TOTALS	118.1	88.0	325.8	-237.8

NOTE 1. ESTIMATED SHRINKAGE FACTOR IS 25%

EARTHWORK BALANCE FROM CONSTRUCTION AT S.N. 053-0159 (WASTE)	142
EARTHWORK BALANCE (SHORTAGE)	-95.8

GUARDRAIL						
LOCATION	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FT POSTS	TRAFFIC BARRIER TERMINAL TYPE 1 (SPECIAL) FLARED	TRAFFIC BARRIER TERMINAL TYPE 6	GUARDRAIL REMOVAL	GUARDRAIL MARKER TYPE A	TERMINAL MARKER DIRECT APPLIED
	FOOT	EACH	FOOT	FOOT	EACH	EACH
IL 116 WEST OF S.N. 053-0070(EX) /S.N. 053-0191 (PR)	40.625	2	2	183	3	1
EAST OF S.N. 053-0070(EX) /S.N. 053-0191 (PR)	65.625	2	2		3	1
CR 24	87.5	1		156	4	1
TOTALS	193.75	5	4	339	10	3