

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				STATE FUNDS 100% STATE STRUCTURE 0014 RURAL
50606701	CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 1	L SUM	1	1
67100100	MOBILIZATION	L SUM	1	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	230	230
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	690	690
78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	395	395
78300100	PAVEMENT MARKING REMOVAL	SQ FT	198	198
X0325969	PORTABLE, VEHICLE MOUNTED, CHANGEABLE MESSAGE BOARD	CAL DA	15	15
X0326880	MESSAGE BOARD VEHICLE DRIVER	HOUR	180	180
X5067501	BRIDGE CLEANING AND PAINTING WARRANTY NUMBER 1	L SUM	1	1
X7010208	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	1	1
Z0007101	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1	1
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1
70600350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	3	3

* SPECIALITY ITEM

13

FILE NAME =	USER NAME = woodhankr1	DESIGNED - RW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
oi\pwwork\pwwork\woodhankr1\0319001\66C61.sht-detailed.dgn	DRAWN - RW	REVISED -	57			(38-5HB-3)BP	IROQUOIS	8	3	
#MODELNAME#	PLT SCALE = 1/8"=1'-0" / in.	CHECKED -	REVISED -			CONTRACT NO. 66C61				
	PLT DATE = 11/15/2012	DATE -	REVISED -			SCALE:	SHEET 1 OF 1 SHEETS	STA. TO STA.	[ILLINOIS] FED. AID PROJECT	