CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION CODE 100% STATE BUREAU CO. 0005 RURAL	LASALLE CO. 0005 RURAL
45100100	CRACK ROUTING (PAVEMENT)	FOOT	106415	77971	28444
45100200	CRACK FILLING	POUND	37244	27288	9956
67100100	MOBILIZATION	L SUM	1	0.75	0.25
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EA	8	4	4
X0326880	MESSAGE BOARD VEHICLE DRIVER	HOUR	160	120	40
X0326907	PORTABLE, VEHICLE MOUNTED, CHANGEABLE MESSAGE SIGN	CAL MO	1	0.75	0.25
X7010600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406 (SPECIAL)	L SUM	1	0.75	0.25

* SPECIALTY ITEMS

• BUREAU / LASALLE

FILE NAME = c:\pw_work\pwidot\carpenterdj\d0321797\D366C66-sht-S00.dgn	USER NAME = carpenterdj	DESIGNED - ___	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE. 80	SECTION 03 CRACK SEAL 2013-2	COUNTY *	TOTAL SHEETS 7	SHEET NO. 3
	PLOT SCALE = 100.0000 ' / in.	DRAWN - ___	REVISED -		SCALE: ___ SHEET NO. __ OF __ SHEETS STA. ___ TO STA. ___			CONTRACT NO. 66C66		
	PLOT DATE = 12/11/2012	CHECKED - ___	REVISED -				ILLINOIS FED. AID PROJECT			
		DATE - ___	REVISED -							