

TABULATION OF GROUND MOUNTED SIGNS

SIGN PANEL NUMBER	SIGN PANEL, TYPE 3			POST SIZE	DISTANCE FROM EOP TO POST*	NO. OF POSTS	POST SPACING (C-C)	SIGN POST LENGTH			STUB POST LENGTH, EACH	STRUCTURAL STEEL SUPPORT-BREAKAWAY	CONCRETE FOUNDATIONS, GROUND MOUNT	REINF. BARS	FUSE PLATE BOLT SIZE	REMOVE CONCRETE FOUNDATION - GM	REMOVE SIGN PANEL, TYPE 3	REMOVE EXIST. SIGN COMPLETE	SIGN PANEL OVERLAY										
	PANEL SIZE (W X H)	TOTAL AREA	IN					X	TOTAL AREA	L1**									L2	L3	IN	EACH	SQ FT	EACH	IN	SQ FT			
	IN	SQ FT																									FT	FT	FT
0-00																			114	X	108	85.50							
0-01																			132	X	120	110.00							
0-02																			90	X	84	52.50							
0-03	120	X	192	160.00	W14X30	20.00	2	6.00	25.02	25.70		3.00	1,701.60	3.80	226.00	3/4" x 2 1/4"	2					1							
0-10																										174	X	150	181.25
0-14	120	X	192	160.00	W14X30	24.50	2	6.00	23.41	23.96		3.00	1,601.10	3.80	226.00	3/4" x 2 1/4"	2						1						
0-21																										120	X	168	140.00
0-22																										180	X	168	210.00
0-31																										138	X	108	103.50
1-01	210	X	162	236.25	W14 X38	17.00	2	10.50	20.35	22.62		3.50	1,898.86	4.18	244.00	3/4" x 2 1/2"	2						1						
1-10	252	X	144	252.00	12x 26	38.00	3	7.35	21.52	21.50	21.70	3.00	1,916.72	4.23	321.00	2/4" x 2 1/2"	2						1						
1-31	138	X	120	115.00	W14X38	41.50	2	6.90	23.90	26.40		3.50	2,177.40	4.18	244.00	5/8" X 2 1/4"	2						1						
2-20	138	X	180	172.50	W12X26	24.00	2	6.90	22.45	22.00		3.00	1,311.70	2.54	214.00	3/4" X 2 1/2"	2						1						
2-21	132	X	192	176.00	W14X30	17.60	2	6.60	23.60	23.90		3.00	1,605.00	3.80	226.00	3/4" X 2 1/4"	2						1						
3-01	216	X	258	387.00	W16X45	34.00	3	6.30	29.90	30.90	31.20	3.50	4,612.50	6.69	390.00	1" X 2 3/4"	3						1						
3-10	216	X	192	288.00	W14X38	37.25	3	6.30	26.20	27.75	29.40	3.50	3,566.30	6.27	366.00	7/8" X 2 1/2"	3						1						
3-20	156	X	144	156.00	W14X30	38.90	2	7.80	20.40	22.50		3.00	1,467.00	3.80	226.00	3/4" X 2 1/4"	2						1						
3-30	156	X	144	156.00	W10X22	16.80	2	7.80	19.45	19.50		3.00	988.90	2.36	184.00	3/4" X 2 1/4"	2						1						
3-31	156	X	72	78.00	W6x15	12.10	2	7.80	15.75	16.10		2.50	552.75	1.40	156.00	1/2" X 1 3/4"	2						1						
7-00	186	X	174	224.75	W16X45	39.00	2	9.30	26.80	27.10		3.50	2,740.50	4.46	260	3/4" X 2 1/2"	2												
Peoria County Total				668.50									6,219.40	13.94	440.00		8.00						4.00						701.50
Tazewell County Total				1,893.00									19,920.93	37.57	2,391.00		20.00						8.00						181.25
TOTAL				2,562									26,140	36	2,266		28						12						883

*NOTE: DISTANCE FROM EDGE OF PAVEMENT TO THE CENTER OF POST NEAREST TO THE EDGE OF PAVEMENT
 ** NOTE: L1 IS THE LENGTH OF THE POST NEAREST TO THE EDGE OF PAVEMENT

USER NAME =	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -
PLOT DATE =	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	VARIOUS	PEO/TAZ	44	10
CONTRACT NO. 68B07			ILLINOIS FED. AID PROJECT	