

COMMITMENTS

No Commitments have been made for this project.

GENERAL NOTES

All Metalizing shall be as specified in the Special Provision for "Field Thermal Spraying Metalizing"
 All beams, brackets and all other structural steel shall be cleaned per Near White Blast Cleaning
 SSPC SP 10 according to the following schedule:

Bridge Locations 1 – 6. All beams, brackets and all other structural steel within 5 feet (as measured along the centerline of the bearing) either side of the deck joints. Bridge 7 shall be 10 feet

Bridge Location 1 – 7. All Fascia beams shall be painted Blue (Munsell No. 10B 3/6)

Bridge Location 1 – 6. All Underside beams shall be painted Blue.

Bridge Location 7. All Underside beams shall be painted Light Grey (Munsell No. 5B 7/1)

Top coat and Sealer shall be from the approved list from table one (1) of the Special Provisions.

AIR MONITORS – None for this project.

QP1 & QP2 Required for this Project.

FILE NAME * March 2013 Metalize.dgn	USER NAME * DEFAULT	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	Commitments and General Notes	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
MODELNAME*	PLOT SCALE * 0.8212 / / in.	DRAWN -	REVISED -			var	04 Bridge Metalizing 2013	Various	20	10	
	PLOT DATE * 12/13/2012	CHECKED -	REVISED -			SCALE: _____ SHEET _____ OF _____ SHEETS STA. _____ TO STA. _____		CONTRACT NO. 60925			
		DATE -	REVISED -			ILLINOIS/REG. AID PROJECT					