

CONSTRUCTION CODE	
STP FUNDING 80% FEDERAL 20% STATE	STP FUNDING 80% FEDERAL 20% STATE
ROADWAY	BRIDGE
0004	0011
S. N. 034-2527	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY		
50200100	STRUCTURE EXCAVATION	CU YD	1480		1480
50800105	REINFORCEMENT BARS	POUND	52,440		52,440
50800515	BAR SPLICERS	EACH	119		119
51500100	NAME PLATES	EACH	1		1
54003000	CONCRETE BOX CULVERTS	CU YD	249		249
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2	
54215553	METAL END SECTIONS 18"	EACH	2	2	
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	5.3	5.3	
60221100	MANHOLES, TYPE A, 5' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	9	9	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12	
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	

• SEE SPECIAL PROVISIONS

FILE NAME * c:\pwork\proj\dot\pwork\p1\032685\0672862-ht-500.dgn
 PLOT DATE * 12/12/12 10:15:16AM
 PLOT DRIVER * PLOTDRVS



USER NAME * aparksg	DESIGNED - MCV	REVISED -
FILE NAME * D672862-ht-500.dgn	DRAWN - CMM	REVISED -
PLOT SCALE * 100.0000 1/1 in.	CHECKED - MTM	REVISED -
PLOT DATE * Dec-18-2012 10:15:16AM	DATE - 12/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
685	113B-4	HANCOCK	57	6
CONTRACT NO. 72B62				
SCALE:	SHEET NO. 4 OF 7 SHEETS	STA.	TO STA.	
ILLINOIS FED. AID PROJECT				