

78001120 PAINT PAVEMENT MARKING, LINE 5"						
		LENGTH	SOLID WHITE EDGE LINE	YELLOW SKIP-DASH	SOLID YELLOW LINE	CENTERLINE TYPE
"FROM" STATION	"TO" STATION	FT	FT	FT	FT	
<b>MENARD COUNTY</b>						
84+70.00	97+62.90	1292.9	2585.8		2585.8	DOUBLE YELLOW
97+62.90	119+77.20	2214.3	4428.6	553.6		SKIP DASH
119+77.20	130+96.00	1118.8	2237.6	279.7	1118.8	NO PASSING
130+96.00	138+81.73	785.7	1571.5	196.4		SKIP DASH
138+81.73 BK	139+88.70 AH	STATION EQUATION				
139+88.70	249+05.00	10916.3	21832.6	2729.1		SKIP DASH
249+05.00	258+00.00	895.0	1790.0	223.8	895.0	NO PASSING
258+00.00	261+00.00	300.0	600.0		600.0	DOUBLE YELLOW
261+00.00	270+00.00	900.0	1800.0	225.0	900.0	NO PASSING
270+00.00	270+19.96	20.0	39.9	5.0		SKIP DASH
270+19.96 BK	270+60.46 AH	STATION EQUATION				
270+60.46	286+50.00	1589.5	3179.1		3179.1	DOUBLE YELLOW
286+50.00	318+00.00	3150.0	6300.0	787.5		SKIP DASH
318+00.00	319+00.00	100.0	200.0		200.0	DOUBLE YELLOW
319+00.00	337+00.00	1800.0	3657.5	450.0		SKIP DASH
337+00.00	342+00.00	500.0	1000.0		1000.0	DOUBLE YELLOW
342+00.00	349+13.70	713.7	1427.4	178.4		SKIP DASH
349+13.70	352+65.00	351.3	702.6	87.8		SKIP DASH
352+65.00	361+80.00	915.0	1830.0	228.8	915.0	NO PASSING
361+80.00	455+62.05	9382.1	18764.1	2345.5		SKIP DASH
455+62.05 BK	455+82.01 AH	STATION EQUATION				
455+82.01	501+39.00	4557.0	9114.0	1139.2		SKIP DASH
501+39.00	512+60.00	1121.0	2242.0	280.3	1121.0	NO PASSING
512+60.00	513+80.00	120.0	240.0		240.0	DOUBLE YELLOW
513+80.00	524+45.00	1065.0	2130.0	266.3	1065.0	NO PASSING
524+45.00	732+15.94	20770.9	41541.9	5192.7		SKIP DASH
732+15.94	732+50.94	35.0	70.0		70.0	DOUBLE YELLOW
732+50.94 BK	732+49.96 AH	STATION EQUATION				
732+49.96	750+02.00	1752.0	3504.0		3504.0	DOUBLE YELLOW
750+02.00	750+37.00	35.0	70.0		70.0	DOUBLE YELLOW
750+37.00	753+22.00	285.0	570.0		570.0	DOUBLE YELLOW
SUBTOTAL		66685.5	133428.5	15169.0	18033.7	
<b>MENARD COUNTY TOTAL</b>		<b>166,632 FEET</b>				

78001120 PAINT PAVEMENT MARKING, LINE 5" (CONTINUED)						
		LENGTH	SOLID WHITE EDGE LINE	YELLOW SKIP-DASH	SOLID YELLOW LINE	CENTERLINE TYPE
"FROM" STATION	"TO" STATION	FT	FT	FT	FT	
<b>MASON COUNTY</b>						
750+37.00	764+39.00	1402.0	2804.0		2804.0	DOUBLE YELLOW
764+39.00	783+73.96	1935.0	3870.0		3870.0	DOUBLE YELLOW
783+73.96	784+49.53	76.0	152.0	19.0		SKIP DASH
784+49.53 BK	33+22.93 AH	STATION EQUATION				
33+22.93	43+14.36	991.0	1982.0	247.8		SKIP DASH
43+14.36	48+39.36	525.0	1050.0	131.3	525.0	NO PASSING - NB
48+39.36	63+15.36	1476.0	2952.0		2952.0	DOUBLE YELLOW
63+15.36	72+60.36	945.0	1890.0	236.3	945.0	NO PASSING - SB
72+60.36	77+74.36	514.0	1028.0	128.5		SKIP DASH
77+74.36	83+15.36	541.0	1082.0	135.3	541.0	NO PASSING - NB
83+15.36	87+78.36	463.0	926.0	115.8		SKIP DASH
87+78.36	91+77.36	399.0	798.0	99.8	399.0	NO PASSING - SB
91+77.36	93+27.36	150.0	300.0	37.5		SKIP DASH
93+27.36	103+71.36	1044.0	2088.0	261.0	1044.0	NO PASSING - NB
103+71.36	106+12.36	241.0	482.0		482.0	DOUBLE YELLOW
106+12.36	115+25.36	913.0	1826.0	228.3	913.0	NO PASSING - SB
115+25.36	162+94.36	4769.0	9538.0	1192.3		SKIP DASH
162+94.36	169+56.79	662.0	1324.0	165.5	662.0	NO PASSING - NB
169+56.79 BK	170+11.3 AH	STATION EQUATION				
170+11.30	172+37.36	226.0	452.0	56.5	226.0	NO PASSING - NB
172+37.36	174+18.36	181.0	362.0		362.0	DOUBLE YELLOW
174+18.36	180+78.36	660.0	1320.0	165.0	660.0	NO PASSING - SB
180+78.36	186+98.36	620.0	1240.0	155.0		SKIP DASH
186+98.36	196+96.36	998.0	1996.0	249.5	998.0	NO PASSING - NB
196+96.36	200+28.36	332.0	664.0		664.0	DOUBLE YELLOW
200+28.36	203+49.36	321.0	642.0	80.3	321.0	NO PASSING - SB
203+49.36	259+30.36	5581.0	11162.0	1395.3		SKIP DASH
259+30.36	263+11.04	381.0	762.0	95.3	381.0	NO PASSING - NB
263+11.04 BK	263+14.43 AH	STATION EQUATION				
263+14.42	270+65.38	751.0	1502.0	187.8	751.0	NO PASSING - NB
SUBTOTAL		27097.0	54194.0	5382.5	19500.0	
<b>MASON COUNTY TOTAL</b>		<b>79,077 FEET</b>				
		<b>TOTAL = 245,709 FEET</b>				

FILE NAME =	USER NAME = sparksgw	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw\work\p\id\dot\sparksgw\10328123\067293-sht-schedule.dgn		DRAWN -	REVISED -					658	D6 RUMBLE STRIP 2013	*	39	4
Default	PLOT SCALE = 100.0000' / 1".	CHECKED -	REVISED -		SCALE: SHEET OF SHEETS STA. TO STA.			CONTRACT NO. 72F93				
	PLOT DATE = Dec-20-2012 10:58:59AM	DATE -	REVISED -					ILLINOIS FED. AID PROJECT				