

SHOULDER SCHEDULE

STATION TO STATION			SIDE	LENGTH FEET	EXCAVATING AND GRADING EXISTING SHOULDER UNIT	AGGREGATE WEDGE SHOULDER, TYPE B TON	HOT-MIX ASPHALT SHOULDERS, 8" SO YD	SHOULDER RUMBLE STRIPS, 8 INCH FOOT	
	TO								
421+21.00	TO	632+79.24	LT & RT	21158	420	1594	18645	40853	
SHELBY/MOULTRIE COUNTY LINE									
632+79.20	TO	633+22.98	LT & RT	44	0.9	3.3	39	87.6	
STA 633+22.98 BK = STA 633+18.57 AH									
633+18.57	TO	650+40.37	LT & RT	1722	34	131	1530	3368	
STA 650+40.37 BK = STA 650+44.78 AH									
650+44.78	TO	782+81.02	LT & RT	13236	259	983	11506	25991	
STA 782+81.02 BK = STA 782+95.55 AH									
782+95.55	TO	822+72.07	LT & RT	3977	78	294	3446	7754	
STA 822+72.07 BK = STA 822+64.12 AH									
822+64.12	TO	842+04.98	LT & RT	1941	38	145	1699	3882	
STA 842+04.98 BK = STA 842+12.93 AH									
842+12.93	TO	1109+43.00	LT & RT	26730	502	1906	22325	51563	
1109+43.00	TO	1111+21.00	LT	178	2	7	79	178	
TOTALS =						1334	5063	59269	133677

HMA AND AGGREGATE SHOULDER OMISSIONS:

STATION	ID	STATION	SIDE
726+63	TO	729+50	LT
841+58	TO	845+70	LT
950+70	TO	951+09	LT
957+01	TO	960+84	LT
1100+16	TO	1105+54	LT
841+92	TO	845+70	RT
950+70	TO	951+09	RT
957+53	TO	960+84	RT
1100+16	TO	1105+54	RT

RUMBLE STRIP OMISSIONS:

STATION	ID	STATION	SIDE
727+87	TO	728+43	LT
950+70	TO	951+09	LT
958+91	TO	959+48	LT
727+87	TO	728+43	RT
950+70	TO	951+09	RT
958+91	TO	959+48	RT

FILE NAME : c:\pwork\pwork\teasleyck\0279424\07	USER NAME : teasleyck	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES				F.A.P. RTE. 770	SECTION .	COUNTY ..	TOTAL SHEETS 8	SHEET NO. 6
PLDT SCALE : 1/80.0000 / in	CHECKED -	REVISED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT CONTRACT NO. 74552		
Default	PLDT DATE : 9/11/2012	DATE -	REVISED -		* 07 HMA SAFETY SHLD 2013-1								
												**Shelby & Moultrie	