

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES		
				SN 060-2051 0011	20% STATE 80% FEDERAL
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	296	296	
28000305	TEMPORARY DITCH CHECKS	FOOT	89	89	
28000400	PERIMETER EROSION BARRIER	FOOT	201	201	
28000500	INLET AND PIPE PROTECTION	EACH	12	12	
28001100	TEMPORARY EROSION CONTROL BLANKET	SQ YD	89	89	
28100107	STONE RIPRAP, CLASS A4	SQ YD	28	28	
28100109	STONE RIPRAP, CLASS A5	SQ YD	453.2	453.2	
28200200	FILTER FABRIC	SQ YD	453.2	453.2	
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	1532	1532	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	85	85	
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	1101	1101	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	109	109	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.5	0.5	
40600300	AGGREGATE (PRIME COAT)	TON	2.1	2.1	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	20	20	

FILE NAME *	USER NAME * #USER#	DESIGNED -	REVISED -
#FILE#		DRAWN -	REVISED -
	PLOT SCALE * #SCALE#	CHECKED -	REVISED -
	PLOT DATE * #DATE#	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 2 OF 7 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
785	136-BR	MADISON	58	4
CONTRACT NO. 76D49				
ILLINOIS FED. AID PROJECT				