

PAVEMENT MARKING SCHEDULE

STATION	THERMOPLASTIC PAVEMENT MARKING LINE - 4"			THERMOPLASTIC PAVMENT MARKING LINE - 8" FOOT	TEMPORARY PAVMENT MARKING LINE - 4" FOOT	TEMPORARY PAVMENT MARKING LINE - 6" FOOT	TEMPORARY PAVMENT MARKING LINE - 8" FOOT	TEMPORARY PAVMENT MARKING LINE - 12" FOOT	PAVMENT MARKING REMOVAL SQ FT	WORK ZONE PAVMENT MARKING REMOVAL SQ FT	SHORT TERM PAVMENT MARKING FOOT	*COMMENTS
	YELLOW SKIP DASH FOOT	SOLID WHITE FOOT	SOLID YELLOW FOOT									
1140+50 TO 1143+08	65	516	258	0	839	0	0	0	280	8.6	25.8	
1143+08 TO 1143+20	3	24	12	0	39	0	0	0	0	0.4	1.2	
1143+20 TO 1145+00	45	360	0	0	405	0	0	0	0	6.0	18.0	
1145+00 TO 1145+11	3	22	0	0	25	0	0	0	8	0.4	1.1	
1145+66 TO 1145+71	2	12	0	*44	14	0	0	0	5	0.2	0.6	CROSSWALK FOR MAINLINE
1145+17 TO 1146+00	21	166	0	0	187	0	0	0	62	2.8	8.3	
1146+00 TO 1146+10	3	20	0	0	23	0	0	0	0	0.3	1.0	
0+00 TO 0+55	0	0	0	0	867	*623	*138	0	0	0	0	CROSSWALK FOR RUNAROUND TC
1140+00	0	0	0	0	0	0	0	*11	0	0	0	STOP BAR FOR RUNAROUND TC
1140+28	0	0	0	0	0	0	0	*10	0	0	0	STOP BAR FOR RUNAROUND TC
1141+96.5	0	0	0	0	0	0	0	*16	0	0	0	STOP BAR FOR RUNAROUND TC
1146+45	0	0	0	0	0	0	0	*11	0	0	0	STOP BAR FOR RUNAROUND TC
SUBTOTAL	140	1120	270	44	2397	623	138	48	355	18.7	56.0	
TOTAL		1530		44	2397	623	138	48	355	19	56	

TRENCH BACKFILL

STATION	TRENCH BACKFILL CUY	LOCATION
PERMANENT		
1143+06.08	7.0	18" CULVERT UNDER PE
1145+40.25	23.3	24" CULVERT UNDER PARK ENTRANCE
TEMPORARY		
1142+32.00	1.0	12" CULVERT UNDER TEMPORARY SW
1144+98.00	21.5	24" CULVERT UNDER PARK ENTRANCE
2+52.00	154.6	3 @ 72" CULVERT UNDER RUNAROUND
TOTAL	207.3	

SODDING SCHEDULE

STATION	SODDING SQ YD		SUPPLEMENTAL WATERING UNIT		NITROGEN FERTILIZER NUTRIENT LBS		PHOSPHOROUS FERTILIZER NUTRIENT LBS		POTASSIUM FERTILIZER NUTRIENT LBS	
	LT	RT	LT	RT	LT	RT	LT	RT	LT	RT
1140+50.00 TO 1140+75.00	8.8	14.7	0.3	0.6	0.1	0.2	0.1	0.2	0.1	0.2
1140+75.00 TO 1141+00.00	20.0	9.4	0.8	0.4	0.2	0.1	0.2	0.1	0.2	0.1
1141+00.00 TO 1141+25.00	23.6	8.3	0.9	0.3	0.3	0.1	0.3	0.1	0.3	0.1
1141+25.00 TO 1141+50.00	25.0	13.8	1.0	0.5	0.3	0.2	0.3	0.2	0.3	0.2
1141+50.00 TO 1141+75.00	25.0	11.0	1.0	0.4	0.3	0.1	0.3	0.1	0.3	0.1
1141+75.00 TO 1142+00.00	26.4	9.2	1.0	0.4	0.3	0.1	0.3	0.1	0.3	0.1
1142+00.00 TO 1142+25.00	26.8	9.2	1.0	0.4	0.3	0.1	0.3	0.1	0.3	0.1
1142+25.00 TO 1142+50.00	25.3	9.2	1.0	0.4	0.3	0.1	0.3	0.1	0.3	0.1
1142+50.00 TO 1142+75.00	23.8	13.3	0.9	0.5	0.3	0.2	0.3	0.2	0.3	0.2
1142+75.00 TO 1143+00.00	11.4	26.9	0.4	1.1	0.1	0.3	0.1	0.3	0.1	0.3
1143+00.00 TO 1143+25.00	7.8	33.6	0.3	1.3	0.1	0.4	0.1	0.4	0.1	0.4
1143+25.00 TO 1143+50.00	17.8	14.7	0.7	0.6	0.2	0.2	0.2	0.2	0.2	0.2
1143+50.00 TO 1143+75.00	29.6	87.5	1.2	3.4	0.4	1.1	0.4	1.1	0.4	1.1
1143+75.00 TO 1144+00.00	24.7	122.8	1.0	4.8	0.3	1.5	0.3	1.5	0.3	1.5
1144+00.00 TO 1144+25.00	11.4	106.3	0.4	4.1	0.1	1.3	0.1	1.3	0.1	1.3
1144+25.00 TO 1144+50.00	13.2	103.9	0.5	4.1	0.2	1.3	0.2	1.3	0.2	1.3
1144+50.00 TO 1144+75.00	14.4	102.8	0.6	4.0	0.2	1.3	0.2	1.3	0.2	1.3
1144+75.00 TO 1145+00.00	15.4	69.3	0.6	2.7	0.2	0.9	0.2	0.9	0.2	0.9
1145+00.00 TO 1145+25.00	16.4	19.2	0.6	0.7	0.2	0.2	0.2	0.2	0.2	0.2
1145+25.00 TO 1145+50.00	16.0	43.1	0.6	1.7	0.2	0.5	0.2	0.5	0.2	0.5
1145+50.00 TO 1145+75.00	16.7	75.1	0.7	2.9	0.2	0.9	0.2	0.9	0.2	0.9
1145+75.00 TO 1146+00.00	18.3	66.9	0.7	2.6	0.2	0.8	0.2	0.8	0.2	0.8
1146+00.00 TO 1146+10.00	9.6	27.4	0.4	1.1	0.1	0.3	0.1	0.3	0.1	0.3
SUB-TOTAL	427.3	997.6	16.7	38.9	5.3	12.4	5.3	12.4	5.3	12.4
ROUNDED TOTAL	1425		56		18		18		18	

TEMPORARY EROSION CONTROL SEEDING SCHEDULE

STATION	TEMPORARY EROSION CONTROL SEEDING LBS		MULCH METHOD II ACRE	
	LT	RT	LT	RT
1140+58.00 TO 1141+02.50	0.0	17.1	0.0	0.1
0+00.00 TO 0+50.00	0.0	19.2	0.0	0.1
0+50.00 TO 0+75.00	0.0	9.9	0.0	0.0
0+75.00 TO 1+00.00	5.3	9.5	0.0	0.0
1+00.00 TO 1+25.00	9.8	8.0	0.0	0.0
1+25.00 TO 1+50.00	8.4	8.0	0.0	0.0
1+50.00 TO 1+75.00	7.5	9.7	0.0	0.0
1+75.00 TO 2+00.00	7.3	10.1	0.0	0.1
2+00.00 TO 2+25.00	6.2	8.4	0.0	0.0
2+25.00 TO 2+50.00	5.9	6.6	0.0	0.0
2+50.00 TO 2+75.00	8.9	7.1	0.0	0.0
2+75.00 TO 3+00.00	11.6	10.4	0.1	0.1
3+00.00 TO 3+25.00	11.0	11.4	0.1	0.1
3+25.00 TO 3+50.00	7.9	10.2	0.0	0.1
3+50.00 TO 3+75.00	5.9	10.3	0.0	0.1
3+75.00 TO 4+00.00	10.2	10.6	0.1	0.1
4+00.00 TO 4+25.00	8.0	10.4	0.0	0.1
4+25.00 TO 4+50.00	0.6	3.8	0.0	0.0
SUB-TOTAL	114.7	180.5	0.6	0.9
ROUNDED TOTAL	296		2	

10 APPLICATIONS OF TEMPORARY EROSION CONTROL SEEDING  
5 APPLICATIONS OF MULCH METHOD II

SIDEWALK SCHEDULE

STATION	SIDEWALK REMOVAL SQ FT	PCC SIDEWALK-4' SQ FT	*TEMPORARY SIDEWALK SQ FT
1140+50.00 TO 1140+65.00	56	100	0
1142+29.75 TO 1142+35.75	0	0	56
1142+74.00 TO 1143+29.88	224	279	0
1143+65.88 TO 1145+10.50	578	723	0
1145+10.50 TO 1145+16.50	0	0	54
1145+16.50 TO 1146+00.00	334	418	0
1146+00.00 TO 1147+27.50	510	638	0
TOTAL	1702	2158	110

\*FYI ONLY - TEMPORARY SIDEWALK IS PAID FOR AS AGGREGATE FOR TEMPORARY ACCESS.

RR 4 SCHEDULE

STATION	LT/RT	STONE RIPRAP, CLASS A4 SQ YD	FILTER FABRIC SQ YD
1142+67.50	LT	16.3	16.3
1144+84.00	RT	5.6	5.6
1145+99.00	RT	5.6	5.6
SUB-TOTAL		27.5	27.5
ROUNDED TOTAL		28	28