

MAINLINE RESURFACING SCHEDULE								
LOCATION			HMA SURFACE REMOVAL, 3/4"	HMA SURFACE REMOVAL, 2 1/4"	BIT. MAT'L PRIME COAT	AGGREGATE PRIME COAT	HMA SURFACE COURSE MIX D, N 70	STRIP REFLECTIVE CRACK CONTROL TREATMENT
			(SQ YD)	(SQ YD)	(TON)	(TON)	(TON)	(FOOT)
0.00	TO	0.10		2464.00	0.77	2.29	192.19	1056.00
0.10	TO	1.80	25930.67		8.11	38.90	3267.26	17952.00
1.88	TO	3.23	20592.00		6.44	30.89	2594.59	14256.00
3.23	TO	3.25		288.89	0.09	0.43	36.40	200.00
3.25	TO	4.90	25168.00		7.88	37.75	3171.17	17424.00
4.91	TO	5.66	11440.00		3.58	17.16	1441.44	7920.00
5.66	TO	6.66		15253.33	4.77	22.88	1921.92	10560.00
6.66	TO	7.92	19219.20		6.01	28.83	2421.62	13305.60
TOTAL			102350	18007	37.7	180	15047	82674

TEMP. RAMP/BUTT JOINT SCHEDULE					
LOCATION	LT/RT	TEMPORARY RAMP	HMA SURFACE REMOVAL - BUTT JOINT	P.C.C SURFACE REMOVAL - BUTT JOINT	COMMENTS
MILE PT.		SQ YD	SQ YD	SQ YD	
0.00		22			BEG. RESURF.
0.31	LT	28	41.67		WHITE OAK LN.
0.31	RT	28	41.67		MERKEL ST.
0.81	LT	37	54.17		STAUNTON RD.
1.07	RT	23	33.33		GREENBRIAR EST.
1.25	RT	34	50.00		LAUREL OAK LN
1.48	RT	48	70.83		GOSHEN
1.80		15	87.00		060-0340
1.88		15	87.00		060-0340
1.91	LT	17	25.00		PIN OAK RD.
3.01	RT	28	41.67		OLD STAUNTON RD.
4.39	RT	34	50.00		GROTEFENDT
4.39	LT	20	29.17		GROTEFENDT
4.90		15	87.00		IL 4
4.91		15	87.00		IL 4
7.14	RT	28		42.00	BOOMERANG DR.
7.92		15	87.00		END RESURF.
TOTAL =		422	873	42	

SIDE ROAD SCHEDULE							
LOCATION	SIDE	LENGTH	WIDTH	BIT. MAT'L PRIME COAT	AGGREGATE PRIME COAT	INCIDENTAL HMA SURFACING	COMMENTS
MILE PT.	LT/RT	(FEET)	(FEET)	(TON)	(TON)	(TON)	
0.31	LT	7.5	50	0.01	0.06	3.50	WHITE OAK LN.
0.31	RT	7.5	50	0.01	0.06	3.50	MERKEL ST.
0.81	LT	7.5	65	0.02	0.08	4.55	STAUNTON RD.
1.07	RT	7.5	40	0.01	0.05	2.80	GREENBRIAR EST.
1.25	RT	7.5	60	0.02	0.08	4.20	LAUREL OAK LN
1.48	RT	7.5	85	0.02	0.11	5.95	GOSHEN
1.91	LT	7.5	30	0.01	0.04	2.10	PIN OAK RD.
3.01	RT	7.5	50	0.01	0.06	3.50	OLD STAUNTON RD.
4.39	RT	7.5	60	0.02	0.08	4.20	GROTEFENDT
4.39	LT	7.5	35	0.01	0.04	2.45	GROTEFENDT
7.14	RT	7.5	75	0.02	0.09	5.25	BOOMERANG DR.
TOTAL =				0.2	1	42	