

# PAVEMENT MARKING SCHEDULE

LOCATION			LENGTH	THERMOPLASTIC PAVEMENT MARKING					RAISED RELFLECTIVE PAVEMENT MARKER REMOVAL	RAISED RELFLECTIVE PAVEMENT MARKERS	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
				4"			12"	24"				
				SOLID WHITE EDGE LINE	SKIP-DASH YELLOW CENTERLINE	SOLID YELLOW CENTER LINE	CROSS WALK	SOLID WHITE STOP BARS				
M.P.	TO	M.P.	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	FOOT	FOOT
EDGE LINE												
0.00	TO	1.78	9398.4	18797					118	118	1880	627
1.84	TO	4.90	16156.8	32314					202	202	3232	1077
4.91	TO	5.66	3960	7920					50	50	792	264
5.66	TO	6.66	5280	10560					66	66	1056	352
6.66	TO	7.92	6652.8	13306					84	84	1332	444
SKIP-DASH CENTER												
0.00	TO	0.62	818		818							
1.05	TO	1.43	502		502							
1.53	TO	1.70	224		224							
1.72	TO	1.85	172		172							
2.33	TO	3.21	1162		1162							
3.25	TO	4.90	2178		2178							
4.90	TO	5.19	383		383							
5.26	TO	7.92	3538		3538							
NPZ EB LANE												
0.45	TO	0.91	2429			2429						
1.27	TO	1.53	1373			1373						
1.70	TO	2.33	3326			3326						
3.05	TO	3.25	1056			1056						
3.81	TO	3.96	792			792						
4.54	TO	4.69	792			792						
4.96	TO	5.06	528			528						
5.19	TO	5.30	581			581						
5.51	TO	5.61	528			528						
7.46	TO	7.59	686			686						
7.89	TO	7.92	264			264						
NPZ WB LANE												
0.62	TO	1.05	2270			2270						
1.43	TO	1.72	1531			1531						
1.85	TO	2.48	3326			3326						
3.21	TO	3.41	1056			1056						
3.98	TO	4.11	686			686						
4.70	TO	4.86	845			845						
5.11	TO	5.26	792			792						
5.42	TO	5.51	475			475						
5.65	TO	5.75	526			526						
7.69	TO	7.79	526			526						
CROSS WALKS												
3.26 (BIKE TRAIL)							52					
5.98 (WINDMILL)							104					
6.16 (DUNCAN)							134					
6.25 (HUMBOLT)							52					
STOP BARS												
4.9 (IL 4)											18	
4.91 (IL 4)											18	
6.16 (DUNCAN)											36	
SUB-TOTALS				82897	8977	24388						
GRAND TOTALS					116262		342	72	520	520	8292	2764