

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE
				0004	0011
				ROADWAY	S.N. 097-0078
20200100	EARTH EXCAVATION	CU YD	1,728	1,728	
⊗ 25000210	SEEDING, CLASS 2A	ACRE	0.45	0.45	
⊗ 25000350	SEEDING, CLASS 7	ACRE	0.45	0.45	
⊗ 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	41	41	
⊗ 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	41	41	
⊗ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	41	41	
⊗ 25000700	AGRICULTURAL GROUND LIMESTONE	TON	1	1	
⊗ 25100115	MULCH, METHOD 2	ACRE	0.45	0.45	
⊗ 25100630	EROSION CONTROL BLANKET	SQ YD	2,184	2,184	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100	
28000400	PERIMETER EROSION BARRIER	FOOT	1,050	1050	
28100109	STONE RIPRAP, CLASS A5	SQ YD	2,500		2,500
28200200	FILTER FABRIC	SQ YD	2,500		2,500
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	202	202	

⊗ SPECIALTY ITEM

PRINT DESIGN - LISA M. BAKER
 CHECK DESIGN - LISA M. BAKER
 CHECK DRAWING - LISA M. BAKER
 DATE 10/12/12



USER NAME: jms
 ESCA PROJECT NO. 988.JI
 PLOT SCALE: 0.3000" = 1' DL
 PLOT DATE: 10/12/2012 6:56:29 AM

DESIGNED: JMS
 DRAWN: HAS
 CHECKED: RDP
 DATE: 10/12

REVISED: -
 REVISED: -
 REVISED: -
 REVISED: -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE SHEET NO. 1 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	4B-1	WHITE	70	3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT AID			CONTRACT NO. 78154	