

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE
				0004	0011
				ROADWAY	S. N. 097-0078
50201102	COFFERDAM (TYPE 1) (LOCATION - 2)	EACH	1		1
50300225	CONCRETE STRUCTURES	CU YD	516.6		516.6
50300255	CONCRETE SUPERSTRUCTURE	CU YD	505.8		505.8
50300260	BRIDGE DECK GROOVING	SQ YD	902		902
50300280	CONCRETE ENCASEMENT	CU YD	11.0		11.0
50300300	PROTECTIVE COAT	SQ YD	1,108		1,108
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	141,070		141,070
50800515	BAR SPLICERS	EACH	814		814
51201800	FURNISHING STEEL PILES HP14x73	FOOT	5,054		5,054
51202305	DRIVING PILES	FOOT	5,054		5,054
51203800	TEST PILE STEEL HP14x73	EACH	4		4
51500100	NAME PLATES	EACH	1		1
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	52		52
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	100	100	

④ SPECIALTY ITEM



ESCA PROJECT NO. 988.11
 PLOT SCALE - 0.1667" = 1'-0"
 PLOT DATE - 10/31/2012

DESIGNED - JMS
 DRAWN - HAS
 CHECKED - RDP
 DATE - 10/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE SHEET NO. 3 OF 6 SHEETS STA. TO STA.

F.A. P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	4B-1	WHITE	70	5
CONTRACT NO. 78154				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT AID				