

## SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: 0005

ITEM NO.	CODE NO.	ITEM	UNIT	QUANTITY
1	20201200*	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	60
2	30300011*	AGGREGATE SUBGRADE IMPROVEMENT	TON	123
3	35101400*	AGGREGATE BASE COURSE, TYPE B	TON	40
4	40600100*	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,445
5	40600300*	AGGREGATE (PRIME COAT)	TON	14
6	40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1,246
7	40600990	TEMPORARY RAMP	SQ YD	109
8	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,296
9	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	834
10	42400800	DETECTABLE WARNINGS	SQ FT	73
11	44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	14,447
12	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	317
13	44000600	SIDEWALK REMOVAL	SQ FT	741
14	44201749*	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	13
15	44201753*	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	22
16	44201757*	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	43
17	44201759*	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	276
18	56109210*	WATER VALVES TO BE ADJUSTED	EACH	2
19	60255500*	MANHOLES TO BE ADJUSTED	EACH	5
20	60610400*	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	317
21	67100100	MOBILIZATION	L SUM	1
22	70300100	SHORT TERM PAVEMENT MARKING	FOOT	300
23	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	100
Δ 24	78000200	THERMOPLASTIC PAVEMENT MARKING LINE 4"	FOOT	6,918
25	X0322102*	TEMPORARY SIDEWALK RAMP	EACH	8
26	X6024240*	INLETS, SPECIAL	EACH	9
27	X6028300*	INLETS TO BE REMOVED, SPECIAL	EACH	9
28	X7010216*	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1

\*REQUIRES SPECIAL PROVISION, GENERAL NOTE OR DETAIL DRAWING

Δ SPECIALTY ITEMS

FILE = S:\PROJECTS\2011\1814211.RFD\sheet\DESIGN\TRANS\cover.ctb.dgn

REVISION	DATE	BY	REMARKS	DRAWN D.L.B.	<b>CITY OF ROCK FALLS</b> <b>DIXON AVENUE RESURFACING PROJECT</b> 2012	 <b>WILLET HOFMANN ASSOCIATES, INC.</b> 809 EAST 2ND STREET, DAVENP, IL 61021-0267 P. 815-284-3141 F. 815-284-3142 W. WWW.WHAINC.COM	<b>DIXON AVENUE</b> <b>SUMMARY OF QUANTITIES</b>		SECTION 11-00136-00-RS	COUNTY WHITESIDE	TOTAL SHEETS	SHEET NO.
				CHECKED J.R.R.			STA. 2+24.25 - 34+74.25		STA.	STA.	19	2
				APPROVED G.E.S.					WHA #: 1014211	DATE: DEC. 14, 2012		