



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 20, 2024

SUBJECT: FAP Route 71 (IL 54)
Project STP-8VQ6(773)
Section 15(W, RS-2) & (15-1)RS-1
DeWitt County
Contract No. 70901
Item No. 51, March 8, 2024 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page i of the Table of Contents to the Special Provisions.
3. Revised page 14 of the Special Provisions.
4. Revised sheets 9, 30, 31, and 48 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

TABLE OF CONTENTS

INTENT OF PROJECT	1
DESCRIPTION OF WORK	1
TRAFFIC CONTROL PLAN	2
TRAFFIC CONTROL & PROTECTION DEVICES (ROAD & SIDEROAD/STREET CLOSURES)	6
TRANSPORTATION OPERATIONS PLAN	6
NOTIFICATION PRIOR TO LANE CLOSURES	6
UNEVEN LANES	7
COOPERATION BETWEEN CONTRACTORS	7
MAINTENANCE OF ROADWAY DRAINAGE	7
GUARDRAIL INSTALLATION TIME	8
GUARDRAIL REMOVAL AND INSTALLATION	8
HAND GRADING	8
HOT-MIX ASPHALT SURFACE REMOVAL	9
HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	10
PAVEMENT PATCHING – CLASS D AND PARTIAL DEPTH	10
STRINGLINE	11
RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	11
PRAIRIE PROTECTION	11
STATUS OF UTILITIES	12
EXISTING STATE-OWNED UTILITIES	14
PATCH FINISHING	14
RAILROAD PROTECTIVE LIABILITY INSURANCE (BDE)	15
STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	16
CONSTRUCTION LAYOUT RESPONSIBILITY	16
STORM SEWER ADJACENT TO OR CROSSING WATER MAIN	16
AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE)	17
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE)	18
CEMENT, TYPE IL (BDE)	19
COMPENSABLE DELAY COSTS (BDE)	19
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	22

Revised February 20, 2024

EXISTING STATE-OWNED UTILITIES

Effective: 04-01-2020

Existing state-owned and maintained underground utilities exist with the right of way. The Department is not a member of JULIE and does not locate its own facilities. The Contractor shall be responsible for securing an approved locating firm to locate all existing Department underground facilities prior to commencing any excavation, per the requirements of Article 803 of the Standard Specifications. Utility locates may be also required outside the project limits for traffic control signing and other items. The Contractor may obtain, on request, plans of existing electrical facilities from the Department. For

further information, the contractor may contact the District Traffic Operations Engineer, Gary Sims, at 217-251-4859.

This work shall not be paid for separately but shall be considered included in the various pay items for which JULIE locations are required.

PATCH FINISHING

Eff. 01-01-24

The surface of the patch shall be hand tined in accordance with article 420.09(e) of the Standard Specifications for Road and Bridge Construction. This work shall be included in the cost of the various pavement patching pay items.

Revised February 20, 2024