



- ### Notes
1. COMPACTION SHALL BE IN ACCORDANCE WITH SECTION 205 OF THE SPECIAL PROVISIONS.
  2. ALL PROPOSED SPECIAL EXCELSIOR BLANKET ARE SHOWN WITH A CIRCLED NUMBER. THE LENGTHS OF EACH OF THESE BLANKETS CAN BE FOUND IN A TABLE ON PAGE 32.
  3. AS SHOWN BY THE DRAWN LIMITS, THE STEEP SLOPES EAST OF THE PROPOSED FILL AND 20' AROUND THE UTILITY TOWER SHALL BE REMOVED FROM THE CONSTRUCTION LIMITS. THIS 0.9 ACRE AREA SHALL NOT REQUIRE CLEARING NOR SEEDING.
  4. THE PROPOSED PERIMETER EROSION BARRIER SHALL BE CONSTRUCTED PRIOR TO EARTH EXCAVATION. PER SECTION 280 OF THE SPECIAL PROVISIONS, ROUTINE MAINTENANCE OF THE BARRIER IS REQUIRED AND IS INCIDENTAL TO THE CONTRACT ITEM.

### Legend

	EXISTING CONTOUR
	PROPOSED CONTOUR
	PROPOSED CONSTRUCTION LIMITS
	BASELINE FOR CROSS SECTIONS
	TREE LINE
	SECTION LINE
	OVERHEAD ELECTRIC LINE
	EDGE OF WATER
	EXISTING GRASS LANE
	BORING LOCATION
	EXISTING STRUCTURE
	PROPOSED EXCELSIOR BLANKET (8' WIDTH)

