

SUMMARY OF QUANTITIES

URBAN
100% STATE
1051

CODE NO.	ITEM	UNIT	TOTAL
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	20
20100500	TREE REMOVAL, ACRES	ACRE	0.5
20200100	EARTH EXCAVATION	CU YD	995
20200410	EARTH EXCAVATION (SPECIAL)	CU YD	50
20800150	TRENCH BACKFILL	CU YD	100
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	17,260
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	270
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	270
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	270
* 25000900	SEEDING, CLASS 1 (SPECIAL)	ACRE	1.7
* 25001750	SEEDING, CLASS 4 (SPECIAL)	ACRE	0.9
* 25001810	SEEDING, CLASS 5 (SPECIAL)	ACRE	0.4
* 25100110	MULCH, METHOD 1	TON	6.0
28000400	PERIMETER EROSION BARRIER	FOOT	1600
28000500	INLET AND PIPE PROTECTION	EACH	7
35100100	AGGREGATE BASE COURSE, TYPE A	TON	860
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	80
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	140
42000300	PORTLAND CEMENT CONCRETE PAVEMENT, 8"	SQ YD	15
42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4 INCH	SQ FT	175
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	75
44000600	SIDEWALK REMOVAL	SQ FT	1970
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	25
44200280	PAVEMENT PATCHING TYPE IV	SQ YD	25
48101200	AGGREGATE SHOULDERS TYPE B	TON	40
50102400	CONCRETE REMOVAL	CU YD	5
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	52

SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		COOK	17	4
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 44917-URBAN 100% STATE 1051				

CODE NO.	ITEM	UNIT	TOTAL
* 56103000	DUCTILE IRON WATER MAIN 6"	FOOT	115
* 56108800	TAPPING VALVES AND SLEEVES 6"	EACH	1
671000100	MOBILIZATION	L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
* A2003120	TREE, CELTIS OCCIDENTALIS WINDY CITY (WINDY CITY HACKBERRY), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	1
* B2001167	TREE, CERCIS CANADENSIS (EASTERN REDBUD) 8' HEIGHT, BALLED AND BURLAPPED	EACH	1
* B2001768	TREE, CRATAEGUS CRUS GALLI VAR. INERMIS "CRUSADER" (CRUSADER THORNLESS COCKSPUR HAWTHORN) 2" CALIPER, BALLED AND BURLAPPED	EACH	7
* A2003920	TREE, FRAXINUS PENNSYLVANICA CIMARRON (CIMARRON ^{GREEN} ASH), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	4
* A2005616	TREE, OSTRYA VIRGINIANA (^{AMERICAN HOPHORNBEAM}), 2" CALIPER, BALLED AND BURLAPPED	EACH	5
* C2001049	SHRUB, CARYOPTERIS X CLANDONENSIS "ARTHUR SIMMONDS" (ARTHUR SIMMONDS BLUEBEARD), 1-GALLON	EACH	77
* C2001120	SHRUB, CEANOTHUS AMERICANUS (NEW JERSEY TEA), CONTAINER GROWN, 3-GALLON	EACH	43
* C2003422	SHRUB, HIBISCUS SYRIACUS "BLUE BIRD" (BLUE BIRD ROSE OF SHARON) 2-1/2' HEIGHT, BALLED AND BURLAPPED	EACH	10
* C2004126	SHRUB, KOLKWITZIA AMABILIS "PINK CLOUD" (PINK CLOUD BEAUTY BUSH) 2' HEIGHT, BALLED AND BURLAPPED	EACH	11
* C2005226	SHRUB, POTENTILLA FRUITICOSA "PINK BEAUTY", (PINK BEAUTY BUSH CINQUEFOIL), CONTAINER GROWN, 2-GALLON	EACH	100
* C2005864	SHRUB, RHUS AROMATICA "GRO-LOW", (GRO-LOW SUMAC), CONTAINER GROWN, 3-GALLON	EACH	201
* C2010924	SHRUB, SYRINGA MEYERI PALIBIN (DWARF KOREAN LILAC), 2' HEIGHT, BALLED AND BURLAPPED	EACH	79
* C2010726	SHRUB, SYMPHORICARPUS X CHENALTII "HANCOCK", (HANCOCK CORALBERRY), CONTAINER GROWN, 3-GALLON	EACH	52
* C2011724	SHRUB, VIBURNUM DENTATUM, (ARROWWOOD VIBURNUM), 2' HEIGHT, BALLED AND BURLAPPED	EACH	20
* C2012336	SHRUB, VIBURNUM LANTANA MOHICAN, (MOHICAN WAYFARING TREE VIBURNUM) 3' HEIGHT, BALLED AND BURLAPPED	EACH	21
* K0030396	PERENNIAL PLANTS, ACHILLEA X "MOONSHINE", (MOONSHINE YARROW), 1-GALLON	EACH	70
* K0030398	PERENNIAL PLANTS, AQUILEGIA CANADENSIS, (AMERICAN COLUMBINE), 1-GALLON	EACH	51

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY AND SCHEDULE OF QUANTITIES
IDOT / IHPA
PULLMAN STATE HISTORIC SITE

SCALE: VERT.
HORIZ.
DATE: 11/08/05

DRAWN BY: DJM
CHECKED BY: PJM