

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 531	2006-012 PCC-PP	WILL	8	6

CONTRACT 60B36

MANHATTAN-MONEE RD

PATCH LOCATION NUMBER	LANE	STATION	Westbound			TYPE
			SIZE (L X W)	AREA (SQ. YD.)		
1	1	108+80	100	4	44.4	IV
2	1	106+00	50	4	22.2	IV
3	1	105+50	90	4	40	IV
4	1	103+60	10	4	4.4	I
5	1	103+10	20	4	8.8	II
6	1	101+50	50	4	22.2	IV
7	1	100+70	30	4	13.3	II
8	1	100+00	150	4	66.6	IV
9	1	99+10	60	4	26.6	IV
10	1	97+70	40	4	17.7	III
11	1	96+20	40	4	17.7	III
12	1	95+80	300	4	133.3	IV
13	1	93+20	70	4	31.1	IV
14	1	92+30	30	4	13.3	II
15	1	91+40	80	4	35.5	IV
16	1	91+40	90	4	40	IV
17	1	89+50	30	12	40	IV
18	1	89+10	50	4	22.2	IV
19	1	83+40	140	12	186.6	IV
20	1	81+60	60	4	26.6	IV
TOTAL					812.5	

MANHATTAN-MONEE RD

PATCH LOCATION NUMBER	LANE	STATION	Westbound			TYPE
			SIZE (L X W)	AREA (SQ. YD.)		
1	1	79+20	80	4	35.5	IV
2	1	76+20	20	5	11.1	II
3	1	76+00	40	4	17.7	III
4	1	75+30	30	12	40	IV
5	1	73+70	70	12	93.3	IV
6	1	73+00	140	4	62.2	IV
7	1	71+60	60	12	80	IV
8	1	66+60	10	12	13.3	II
9	1	55+50	50	4	22.2	IV
10	1	53+80	40	4	17.7	III
11	1	51+70	60	4	26.6	IV
12	1	46+80	130	12	173.3	IV
13	1	45+20	120	3	40	IV
14	1	35+90	30	12	40	IV
15	1	32+80	60	4	26.6	IV
16	1	24+10	40	2	8.8	II
17	1	22+80	120	4	53.3	IV
18	1	21+20	170	4	75.5	IV
19	1	13+70	70	4	31.1	IV
20	1	11+60	210	4	93.3	IV
24		3+70	50	4	22.2	IV
TOTAL					983.7	

SCHEDULE TOTALS

CLASS D PATCHES TYPE I	35.3 SQ YD
CLASS D PATCHES, TYPE II	226.4 SQ YD
CLASS D PATCHES, TYPE III	328.8 SQ YD
CLASS D PATCHES, TYPE IV	3025.2 SQ YD
TOTAL	3615.7 SQ YD

ILLINOIS DEPARTMENT OF TRANSPORTATION
**MANHATTAN-MONEE ROAD
PAVEMENT PATCHING SCHEDULE
2 OF 2**