

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1602 *		COOK	38	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
*(0405-1 & 0506-2) RS-1				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		1000 100% STATE	1000 50% STATE 50% VILLAGE	1000 100% VILLAGE		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	34	33	1			
40600300	AGGREGATE (PRIME COAT)	TON	148	147	1			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	23	22	1			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1165	1165				
40600990	TEMPORARY RAMP	SQ YD	1165	1165				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	150	150				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	6215	6125	90			
42001300	PROTECTIVE COAT	SQ YD	427	375		52		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	125	125				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	73856	72850	1006			
44000600	SIDEWALK REMOVAL	SQ FT	125	125				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1230	1074		156		
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1390	1390				
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	10540	10540				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	350	350				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	560	560				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	477	477				
55039700	STORM SEWERS TO BE CLEANED	FOOT	1500	1500				
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	10	10				
60253000	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1				
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1				
60264130	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	1	1				
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	3	3				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		1000 100% STATE	1000 50% STATE 50% VILLAGE	1000 100% VILLAGE		
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	20	19	1			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11950	11950				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	760	760				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	38100	38100				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2400	2400				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2900	2900				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	670	670				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4000	4000				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	760	760				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	38100	38100				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2400	2400				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2900	2900				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	670	670				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	811	811				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	487	487				
* 81400115	HANDHOLE TO BE ADJUSTED	EACH	2	2				
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	3	3				

\*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

12/21/2006 10:58:00 AM