F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
343	*	COOK	283	6
STA. 9+713.000	TO STA. 10+151.000			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		
* 70D-Y-B-R & 70HB-R-1			62897	

SUMMARY OF QUANTITIES

IL ROUTE 68 @ US 14
IDOT PROJECT * D-91-097-05

ITEM *	ITEM DESCRIPTION	UNIT	URBAN 80% FED. 20% STATE QUANTITY	F ROADWAY J000-2A	F STRUCTURE IL 68 OVER US 14 X271-2A	BRF STRUCTURE IL 68 OVER UPRR X171-5B	F TRAFFIC SIGNALS Y031-1F	F MSE AND RETAINING WALLS Y007	F HIGHWAY LIGHTING Y030-1E	100% VILLAGE OF PALATINE Y031-30
M5870300	CONCRETE SEALER	SQ M	57			57				
M5910100	GEOCOMPOSITE WALL DRAIN	SQ M	229		75			154		
M6011100	PIPE UNDERDRAINS FOR STRUCTURES 100MM	METER	109					109		
M6020185	CATCH BASINS, TYPE A, 1.2M DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	2						
M6021405	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1						
M6021410	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1						
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	4	4						
60208230	CATCH BASINS, TYPE C, TYPE 23 FRAME AND GRATE	EACH	1	1						
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	3	3						
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1	1						
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	1	1						
60247900	JUNCTION CHAMBER, SPECIAL	EACH	1	1						
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	1						
60255500	MANHOLES TO BE ADJUSTED	EACH	3	3						
60402210	GRATES, TYPE 8	EACH	1	1						
60403500	GRATES, TYPE B	EACH	2	2						
60500050	REMOVING CATCH BASINS	EACH	1	1						
60500060	REMOVING INLETS	EACH	2	2						
M6060010	CLASS SI CONCRETE (OUTLET)	CU M	8.9	8.9						
M6060015	CLASS SI CONCRETE (INLET)	CU M	2.0	2.0						
M6060290	CONCRETE GUTTER, TYPE B	METER	174.2	174.2						
M6060500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30	METER	75.2	75.2						
M6060615	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.45 (MODIFIED)	METER	153.6	153.6						
M6060700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60	METER	424.0	424.0						
M6011005	PIPE UNDERDRAINS, FABRIC LINED TRENCH 100 MM	METER	314.0	314.0						
M6062100	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-15.15	METER	19.7	19.7						
M6063600	CONCRETE MEDIAN SURFACE, 100MM	SQ M	55	55						
M6064120	CONCRETE MEDIAN, TYPE SB-15.30 (MODIFIED)	SQ M	5	5						
M6064170	CONCRETE MEDIAN, TYPE SB-15.45 (MODIFIED)	SQ M	110	110						
M6066000	CORRUGATED MEDIAN	SQ M	255	255						
* M6300100	STEEL PLATE BEAM GUARD RAIL, TYPE A	METER	858.8	858.8						
* M6300130	STEEL PLATE BEAM GUARD RAIL, TYPE D	METER	79.8	79.8						
* M6370155	CONCRETE BARRIER, SINGLE FACE, 815 MM HEIGHT	METER	22.8	22.8						
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	3	3						
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8	8						
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	5	5						
M6320030	GUARDRAIL REMOVAL	METER	681	681						
M6640100	CHAIN LINK FENCE, 1.2 METER	METER	71	71						
M6640320	CHAIN LINK FENCE, 1.8 METER ATTACHED TO STRUCTURE	METER	107					107		
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	7	7						
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	16	16						
67100100	MOBILIZATION	L SUM	1	1						
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1				1			
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1						
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1				1			
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1				1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1				1			

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

Rev.

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 68

SUMMARY OF QUANTITIES - 3

SCALE NTS DRAWN BY RDT
DATE OCTOBER, 2006 CHECKED BY PK

...\Art\Sheets\68Sheet1.dgn 10/12/2006 5:02:24 PM