CONTRACT NO. 64583

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
567	34X-BR	DEKALB	90	14
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

X0323684 RELOCATE WATER VALVE

EACH	LOCATION
1	142+78, 38' LT
1	TOTAL

X0324886 CONDUIT INSTALLED, 1 1/4" DIA., NON-METALLIC

FOOT	LOCATION
270	134+70, 27' LT - 137+40, 30' LT
270	137+40, 30' LT - 140+10, 32' LT.
28	140+10, 32' LT - SN 019-0044
12	SN 019-0044 - 141+65 - 32' LT
150	141+65, 32' LT - 143+15 - 32' LT
730	TOTAL

X0930400 STORM SEWER WATER MAIN 12"

FOOT	LOCATION
56	134+75 TO 135+33.3, 32.2' RT
80	135+33.3 TO 136+15.7, 31.1' RT
27	136+15.7 TO 136+43.9, 31.1' RT
74	136+43.9 TO 137+20, 29.75' RT
78	137+20 TO 138+00, 28.75' RT
68	138+00 TO 138+70, 27.5' RT
23	139+99 TO 140+24, 27.5 RT
6	139+99
3	141+70 TO 141+75, 23.5' RT
37	141+75 TO 142+15.04, 27.5' RT
3	142+15.04 RT
456	TOTAL

X8730402 ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 19 12 PAIR

FOOT	LOCATION
270	134+70, 27' LT - 137+40, 30' LT
270	137+40, 30' LT - 140+10, 32' LT.
28	140+10, 32' LT - SN 019-0044
118	SN 019-0044
12	SN 019-0044 - 141+65 - 32' LT
150	141+65, 32' LT - 143+15 - 32' LT
848	TOTAL

XX004051 LIGHT POLE, ORNAMENTAL

EACH	LOCATION
1	135+78.72, 42' LT
1	136+99.67, 42' LT
1	138+30.12, 42' LT
3	TOTAL

XX004716 LUMINAIRE, METAL HALIDE, SPECIAL, TYPE III, 175 WATT

EACH	LOCATION
2	135+78.72, 42' LT
2	136+99.67, 42' LT
2	138+30.12, 42' LT
6	TOTAL

50800515 BAR SPLICERS

EACH	LOCATION
21	140+59.60, 62' RT - 140+59.60, 62' LT
21	TOTAL

BIKE PATH

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION	
1	138+77 - 139+00	(STAGE I)
1	142+00 - 142+23	(STAGE I)
2	TOTAL	

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION	
1	139+77 - 139+00	(STAGE II)
1	142+00 - 142+23	(STAGE II)
2	TOTAL	

Z0041700 PLUG EXISTING STORM SEWERS

EACH	LOCATION
1	140+27, 17' LT
1	142+05, 14.19' LT
2	TOTAL

REVISIONS	
NAME	DATE
IDOT REVIEW	10/25/06
IDOT REVISIONS	12/13/06
IDOT REVISIONS	2/01/07

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP RTE 567 (IL RTE 38)
SECTION 34X-BR
DEKALB COUNTY

SCALE: VERT. HORIZ.
DATE 10/24/05

DRAWN BY SUTHEARD
CHECKED BY BOTT

GREENIE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
CIVIL/STRUCTURAL/ENVIRONMENTAL
KNOWLEDGE/EXPERIENCE/SERVICE
PROFESSIONAL DESIGN FIRM NO. 184-000175
PROFESSIONAL & STRUCTURAL ENGINEERING CORPORATION
(217) 753-8844, (217) 753-1221 W.L.E.MAIL - <info@greeniebradford.com>

COMPUTER FILE NO. D10800CVR

PROJECT 05198
10/25/06-CSJ

PLOT DATE = 2/2/2007
FILE NAME = $FILEL$
PLOT SCALE = $SCALE$
PLOT BY = $USER$
OPERATOR = $USER$