

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	211-J	STEPHENSON	64	4
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNITS	TOTAL
			80% Fed 20% State MINOR STRUCTURE Y007
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	2536
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	50
50800105	REINFORCEMENT BARS	POUND	17420
50800515	BAR SPLICERS	EACH	45
51500100	NAME PLATES	EACH	1
54003000	CONCRETE BOX CULVERTS	CU YD	86.1
54205470	PIPE CULVERTS, CLASS D, TYPE 1, EQUIVALENT ROUND-SIZE 15"	FOOT	60
54214290	END SECTIONS, EQUIVALENT ROUND-SIZE 15"	EACH	2
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	300
63200310	GUARDRAIL REMOVAL	FOOT	465
63500105	DELINEATORS	EACH	2
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	8
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70106500	TRAFFIC TEMPORARY BRIDGE SIGNALS	EACH	1
70106700	TEMPORARY RUMBLE STRIP	EACH	12

\* SPECIALTY ITEMS

SUMMARY OF QUANTITIES

PLOT DATE = Wed Dec 28 09:28:53 2006  
 FILE NAME = C:\p\civ\1105\1105.dwg  
 PLOT SCALE = 3/8" = 1' / IN.  
 REFERENCE = 01185