

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
-30L	2LT-1	STEPHENSON	64	10
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

UNIT	LOCATION	OFFSET	REMARKS
11	374+47	69' LT	
15	374+59	66' LT	
11	374+91	49' LT	
12	374+92	47' LT	
10	374+95	43' LT	
13	374+95	43' LT	
9	374+95	66' LT	
9	375+00	78' LT	
12	375+02	47' LT	
13	375+94	48' LT	
<hr/>			
115	TOTAL		

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)

UNIT	LOCATION	OFFSET	REMARKS
26	374+41	64' LT	
28	374+42	68' LT	
19	374+64	69' LT	
18	375+93	43' LT	
<hr/>			
91	TOTAL		

20200100 EARTH EXCAVATION

CUB. YD.	LOCATION	TO	OFFSET	REMARKS
5916	370+00	389+50	LT & RT	
<hr/>				
5916	TOTAL			

25000210 SEEDING CLASS 2A

ACRE	LOCATION	TO	OFFSET	REMARKS
0.9	370+00	389+50	LT	FORESLOPES
1.0	370+00	389+50	RT	FORESLOPES
<hr/>				
2.0	TOTAL			

25000310 SEEDING CLASS 4

ACRE	LOCATION	TO	OFFSET	REMARKS
0.56	370+00	389+50	LT	BACKSLOPES
0.41	370+00	389+50	RT	BACKSLOPES
<hr/>				
0.97	TOTAL			

25000750 MOWING

ACRE	LOCATION	TO	OFFSET	REMARKS
1.46	370+00	389+50	LT	
1.41	370+00	389+50	RT	
<hr/>				
2.87	TOTAL			

25100115 MULCH METHOD 2

ACRE	LOCATION	TO	OFFSET	REMARKS
1.46	370+00	389+50	LT	
1.41	370+00	389+50	RT	
<hr/>				
2.87	TOTAL			

25100630 EROSION CONTROL BLANKET

SQ. YD.	LOCATION	TO	OFFSET	REMARKS
1150	372+50	384+00	LT	
950	373+00	382+50	RT	
232	387+18	389+50	LT	
<hr/>				
2332	TOTAL			

28000250 TEMPORARY EROSION CONTROL SEEDING

POUND	LOCATION	TO	OFFSET	REMARKS
1148	370+00	389+50	LT & RT	4 APPLICATIONS IF APPLICABLE
<hr/>				
1148	TOTAL			

28000300 TEMPORARY DITCH CHECKS

EACH	LOCATION	TO	OFFSET	REMARKS
1	371+50		RT	
9	372+50	375+00	LT	30' SPACING
7	373+00	374+84.6	RT	30' SPACING
13	375+00	384+00	LT	75' SPACING
11	374+84.6	382+50	RT	75' SPACING
4	387+18	389+50	LT	75' SPACING
1	384+00		RT	
1	385+50		RT	
1	385+50		LT	
1	387+00		RT	
1	388+50		RT	
<hr/>				
50	TOTAL			

28000400 PERIMETER EROSION BARRIER

EQFT	LOCATION	TO	OFFSET	REMARKS
300	374+50	375+50	LT	
75	374+50		RT	
75	375+50		RT	
<hr/>				
450	TOTAL			

28000500 INLET AND PIPE PROTECTION

EACH	LOCATION	OFFSET	REMARKS
1	370+58.0	LT	
<hr/>			
1	TOTAL		

35100100 AGGREGATE BASE COURSE TYPE A

TON	LOCATION	TO	OFFSET	REMARKS
47	373+00.0	376+50.0	LT	Assume 4" build up for Stage I
<hr/>				
47	TOTAL			

35101400 AGGREGATE BASE COURSE TYPE B

TON	LOCATION	TO	OFFSET	REMARKS
63	370+88		LT	FE (8" THICKNESS)
31	385+37	385+62		10" Thickness 13' x 25' Temporary Patch
31	385+37	385+62		10" Thickness 13' x 25' Temporary Patch
<hr/>				
125	TOTAL			

40603310 HOT MIX ASPHALT SURFACE COURSE MIX "C" N 50

TON	LOCATION	TO	OFFSET	REMARKS
128	373+00	389+50	LT	Leave 3.5' Shoulder for Stage II except patch area
15	373+50	376+50	LT	3.5' Shoulder for Temp Pavement/Stage I
141	373+00	389+50	RT	
<hr/>				
284	TOTAL			

40603345 HOT MIX ASPHALT SURFACE COURSE MIX "D" N 90

TON	LOCATION	TO	OFFSET	REMARKS
17	374+67.12	375+02.12		3" applied in 2 lifts
12	385+37	385+62		3" applied in 2 lifts
<hr/>				
29	TOTAL			

40800050 INCIDENTAL HOT-MIX SURFACING

TON	LOCATION	TO	OFFSET	REMARKS
6	385+37	385+62		3" Thickness 13' x 25' Temporary Patch
6	385+37	385+62		3" Thickness 13' x 25' Temporary Patch
<hr/>				
12	TOTAL			

42001200 PAVEMENT FABRIC

SQ. YD.	LOCATION	TO	OFFSET	REMARKS
101	374+67.12	375+02.12		
72	385+37	385+62		
<hr/>				
173	TOTAL			

44200976 CLASS B PATCHES TYPE IV 10 INCH

SQ. YD.	LOCATION	TO	OFFSET	REMARKS
101	374+67.12	375+02.12		
72	385+37	385+62		
<hr/>				
173	TOTAL			

44213200 SAW CUTS

EQFT	LOCATION	TO	OFFSET	REMARKS
113	374+67.12	375+02.12		
103	385+37	385+62		
<hr/>				
216	TOTAL			

48101200 AGGREGATE SHOULDERS TYPE B

TON	LOCATION	TO	OFFSET	REMARKS
31	371+16	373+00	LT	6" THICKNESS
26	371+50	373+00	RT	6" THICKNESS
<hr/>				
57	TOTAL			

48203021 HOT MIX ASPHALT SHOULDERS 6"

SQ. YD.	LOCATION	TO	OFFSET	REMARKS
1144	373+00	389+50	LT	Leave 3.5' Shoulder for Stage II except patch area
136	373+00	376+50	LT	3.5' Shoulder for Temp Pavement/Stage I
1256	373+00	389+50	RT	
<hr/>				
2536	TOTAL			

PLOT DATE = Tue Jan 16 10:58:03 2007
 FILE NAME = c:\p\proj\p21105\41105.dgn
 PLOT SCALE = 50.0000 / 1 IN.
 REFERENCE = #REF#